

PAVING SCHEDULE

STATION TO STATION	LENGTH	COMMENT	WIDTH OF RESURFACING (PAVEMENT PLUS HMA SHOULDERS)	HOT-MIX ASPHALT PAVEMENT(FULL DEPTH), 16 1/4"	SUBBASE GRANULAR MATERIAL, TYPE B 12"	HOT-MIX ASPHALT SHOULDERS, 8"	AGGREGATE SHOULDERS, TYPE B, 6"	HOT-MIX BASE COURSE, 14"	SUBBASE GRANULAR MATERIAL, TYPE C	POLYMERIZED HMA SURFACE, MIX "D", N105	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE WEDGE SHOULDER, TYPE B
LOCATION	FOOT		FOOT	SO YD	SO YD	SO YD	SO YD	SO YD	TON	TON	SO YD	GALLON	TON
ABANDONED RR													
WESTBOUND													
118+00.00 TO 120+15.00	215.00		40.0							107	956	96	
120+15.00 TO 122+31.00	216.00	OLD BRIDGE	•	576	1032	384	48		180				
122+31.00 TO 123+00.00	69.00		40.0							34	307	31	
EASTBOUND													
119+00.00 TO 120+55.00	155.00		40.0							77	689	69	
120+55.00 TO 122+71.00	216.00	OLD BRIDGE	•	576	1032	144	48	240	98				
122+71.00 TO 124+00.00	129.00		40.0							64	573	57	
II 121 BRIDGES													
WESTBOUND													
139+25.00 TO 141+66.89	241.89		40.0							120	1075	108	11
141+66.89 TO 143+73.53	206.64	BRIDGE	40.0										
143+73.53 TO 146+75.00	301.47		40.0							150	1340	134	13
EASTBOUND													
138+50.00 TO 142+08.00	358.00		40.0							196	1591	159	15
142+08.00 TO 144+18.54	210.54	BRIDGE	40.0										
144+18.54 TO 147+50.00	331.46		40.0							173	1473	147	14
EMBARRAS RIVER BRIDGES													
WESTBOUND													
152+75.00 TO 154+51.50	176.50		40.0							92	784	78	8
154+51.50 TO 161+92.50	741.00	BRIDGE	40.0										
161+92.50 TO 166+00.00	407.50		40.0							240	1811	181	17
EASTBOUND													
153+75.00 TO 154+51.50	76.50		40.0							41	340	34	3
154+51.50 TO 161+92.50	741.00	BRIDGE	40.0										
161+92.50 TO 166+00.00	407.50		40.0							204	1811	181	17
TOTALS	1650			1152	2064	528	96	240	279	1499	12750	1275	98

• (18-47-VB)K,(18-47B,18-47B)BR

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
ct:\pw\work\p\dot\steffenmk\d0186453\d74466-sh1-sch.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = 8/20/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NA SHEET NO. 3 OF 6 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	•	CUMBERLAND	147	14
CONTRACT NO. 74466			ILLINOIS FED. AID PROJECT	