

BRIDGE APPROACH SCHEDULE

STATION TO STATION	WIDTH FOOT	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) SQ YD	PAVEMENT REMOVAL* SQ YD	APPROACH SLAB REMOVAL SQ YD	PIPE DRAINS 4" FOOT
ABANDONED RR BRIDGES					
WESTBOUND					
120+15.00 TO 120+45.00	40.00			133.3	
122+01.00 TO 122+31.00	40.00			133.3	
EASTBOUND					
120+55.00 TO 120+85.00	40.00			133.3	
122+41.00 TO 122+71.00	40.00			133.3	
I I 121 BRIDGES					
WESTBOUND					
141+66.89 TO 141+72.89	40.00	26.7	26.7	133.3	125.0
143+67.53 TO 143+73.53	40.00	26.7	26.7	133.3	125.0
EASTBOUND					
142+08.00 TO 142+14.00	40.00	26.7	26.7	133.3	125.0
144+12.54 TO 144+18.54	40.00	26.7	26.7	133.3	125.0
EMBARRAS RIVER BRIDGES					
WESTBOUND					
154+51.50 TO 154+57.50	38.00	25.3	25.3	120.0	135.0
161+86.50 TO 161+92.50	38.00	25.3	25.3	120.0	135.0
EASTBOUND					
154+51.50 TO 154+57.50	38.00	25.3	25.3	120.0	135.0
161+86.50 TO 161+92.50	38.00	25.3	25.3	120.0	135.0
TOTALS		208.0	208.0	1546.4	1040.0

* APPROACH SLAB THICKNESS IS 16.25". PAVEMENT THICKNESS IS 13.5"

SEEDING SCHEDULE

LOCATION	SEEDING, CLASS 2 ACRE	NITROGEN FERTILIZER POUND	PHOSPHORUS FERTILIZER POUND	POTASSIUM FERTILIZER POUND	AGRICULTURAL GROUND LIMESTONE TON	MULCH, METHOD 2 ACRE	TEMPORARY EROSION CONTROL SEEDING POUND	SEEDING, CLASS 7 ACRE
ABANDONED RR-NORTH SLOPE	1.90	171	171	171	3.80	1.90	570	
ABANDONED RR-SOUTH SLOPE	1.10	99	99	99	2.20	1.10	330	
ABANDONED RR-MEDIAN: STAGE 1								0.25
TEMP CONSTR ACCESS REMOVAL	0.50	45	45	45	1.00	0.50	150	
TOTALS	3.5	315.0	315.0	315.0	7.0	3.5	1050.0	0.25

MOWING SCHEDULE

STATION TO STATION	LENGTH FEET	WIDTH (APPROX) FEET	MAINTENANCE MOWING ACRE
MEDIAN			
573+00 TO 575+54	254.38	60	0.4
80+00 TO 181+50	10150.00	60	14.1
EASTBOUND			
162+00 TO 180+00	1800.00	40	1.7
WESTBOUND			
573+00 TO 575+55	254.80	40	0.2
80+00 TO 115+00	3500.00	40	3.2
162+00 TO 180+00	1800.00	40	1.7
SUB TOTAL			21.2
TOTAL AREA TO BE MOWED FOUR TIMES			TOTAL 84.8

(18-47-VBK,(18-47B,18-47B)BR

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
ei:\pw\work\p\dot\stefenmk\d0186453\d74466-sh-t-sch.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = 8/20/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NA SHEET NO. 4 OF 6 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	*	CUMBERLAND	147	15
CONTRACT NO. 74466			ILLINOIS FED. AID PROJECT	