

PAVEMENT MARKING SCHEDULE

STATION TO STATION			LENGTH	PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING - LINE 4"	PAINT PAVEMENT MARKING - LINE 6"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER(BRIDGE)
			FOOT	SQ FT	FOOT	FOOT	EACH	EACH
WESTBOUND								
81+00.00	TO	118+00.00	3700.00	2929	7400	925		
118+00.00	TO	120+15.00	215.00	170	860	108	6	
120+15.00	TO	122+31.00	216.00	171	864	108	6	
122+31.00	TO	123+00.00	69.00	55	276	35	2	
123+00.00	TO	139+25.00	1625.00	1286	3250	406		
139+25.00	TO	141+66.89	241.89	191	968	121	6	
141+66.89	TO	143+73.53	206.64	164	827	103		6
143+73.53	TO	146+75.00	301.47	239	1206	151	8	
146+75.00	TO	152+75.00	600.00	475	1200	150		
152+75.00	TO	154+51.50	176.50	140	706	88	6	
154+51.50	TO	161+92.50	741.00	587	2964	371		20
161+92.50	TO	166+00.00	407.50	323	1630	204	10	
166+00.00	TO	183+00.00	1700.00	1346	3400	425		
EASTBOUND								
571+00.00	TO	575+54.38	454.38	360	909	114		
80+00.00	TO	119+00.00	3900.00	3169	7800	975		
119+00.00	TO	120+55.00	155.00	129	620	78	4	
120+55.00	TO	122+71.00	216.00	185	864	108	6	
122+71.00	TO	124+00.00	129.00	113	516	65	4	
124+00.00	TO	138+50.00	1450.00	1299	2900	363		
138+50.00	TO	142+08.00	358.00	328	1432	179	10	
142+08.00	TO	144+18.54	210.54	197	842	105		6
144+18.54	TO	147+50.00	331.46	318	1326	166	8	
147+50.00	TO	153+75.00	625.00	612	1250	156		
153+75.00	TO	154+51.50	76.50	77	306	38	2	
154+51.50	TO	161+92.50	741.00	756	2964	371		20
161+92.50	TO	166+00.00	407.50	424	1630	204	10	
166+00.00	TO	178+00.00	1200.00	1275	2400	300		
TOTALS				17317	51309	6414	88	52

PAVEMENT PATCHING SCHEDULE

LOCATION	PAVEMENT PATCHING, TYPE I 14 INCH	PAVEMENT PATCHING, TYPE II 14 INCH	PAVEMENT PATCHING, TYPE III 14 INCH	PAVEMENT PATCHING, TYPE IV 14 INCH	PARTIAL DEPTH REMOVAL ( VARIABLE DEPTH)	PARTIAL DEPTH PATCHING
	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON
WESTBOUND	6	51	28	170	110	42
EASTBOUND	2	16	9	57	37	14
TOTALS	8	67	37	227	147	56

PIPE UNDERDRAIN SCHEDULE

LOCATION	PIPE UNDERDRAINS, 6"	PIPE UNDERDRAINS, 6" ( SPECIAL)	CLASS SI CONCRETE ( OUTLET)	REINFORCEMENT BARS
	FOOT	FOOT	CU YD	POUND
120+55 TO 122+71 ( EASTBOUND)	432.00	40	3	71
120+15 TO 122+31 ( WESTBOUND)	432.00	40	3	71
TOTAL	864.0	80.0	6.0	142.4

• (18-47-VB)K,(18-47B,18-47B)BR