

FUNDING:	80% FEDERAL/ 20% STATE		
LOCATION:	URBAN		
COUNTY:	WILLIAMSON		
ROUTE:	FAP 331 (IL 13)	FAP 331 (IL13/IL37 INTERSECTION)	FAP 331 (IL 13)
CONST TYPE CODE:	0003	0003	0021

CODE NUMBER	PAY ITEM DESCRIPTION	UNIT	PROJECT TOTAL QUANTITY	ROADWAY	ROADWAY	SIGNALS & LIGHTING
55201500	STORM SEWERS JACKED IN PLACE, 42"	FOOT	117	117		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2		
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60224459	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60224480	MANHOLES, TYPE A, 9'-DIAMETER, TYPE 15 FRAME AND LID	EACH	1	1		
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2	2		
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1	1		
60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	1	1		
60500060	REMOVING INLETS	EACH	13	10	3	
60600605	CONCRETE CURB, TYPE B	FOOT	351	351		
60602500	CONCRETE GUTTER, TYPE A	FOOT	440	440		
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	932	932		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	129	129		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2,643	2,178	465	

FILE NAME : c:\pwwork\pwwork\kellykd\0184451\78203-1\sh-t-sched.dgn
 USER NAME : #USER#
 PLOT SCALE = 100.0000 / in.
 PLOT DATE = 5/10/2012

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
 SHEET 6 OF 13**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(IX-11R-5,RS-3,N-5,TS-4	WILLIAMSON	288	10
ILLINOIS FED. AID PROJECT			CONTRACT NO. 78203	