

FUNDING:	80% FEDERAL/ 20% STATE		
LOCATION:	URBAN		
COUNTY:	WILLIAMSON		
ROUTE:	FAP 331 (IL 13)	FAP 331 (IL13/IL37 INTERSECTION)	FAP 331 (IL 13)
CONST TYPE CODE:	0003	0003	0021

CODE NUMBER	PAY ITEM DESCRIPTION	UNIT	PROJECT TOTAL QUANTITY	ROADWAY	ROADWAY	SIGNALS & LIGHTING
X 81028380	UNDERGROUND CONDUIT, PVC, 3 1/2" DIA.	FOOT	174			174
X 81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	141			141
X 81400100	HANDHOLE	EACH	9			9
X 81500100	GULFBOX JUNCTION	EACH	3			3
X 81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	1,284			1,284
X 82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	10			10
X 82500335	LIGHTING CONTROLLER, MOUNTED, 240VOLT, 100AMP PEDESTAL	EACH	1			1
X 83600350	LIGHT POLE FOUNDATION, METAL, 11" BOLT CIRCLE, 8"X6'	EACH	1			1
X 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1			1
X 86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	1			1
X 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,407			1,407
X 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,492			2,492
X 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,941			1,941

X SPECIALTY ITEM

FILE NAME :	USER NAME : #USER#	DESIGNED -	REVISED -
c:\pwork\pwork\kell\jgk\0104451\78203\shhtrschad.dgn		DRAWN -	REVISED -
PLOT SCALE : 1/8"=1'-0"		CHECKED -	REVISED -
PLOT DATE : 5/10/2012		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SHEET 9 OF 13			
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(IX-DR-5,RS-3,N-5,TS-4	WILLIAMSON	288	13
ILLINOIS FED. AID PROJECT CONTRACT NO. 78203				