

## CURB & GUTTER - MEDIAN REMOVAL

LOCATION STA TO STA	COMBINATION C&G REMOVAL	MEDIAN REMOVAL	MEDIAN SURFACE REMOVAL	ISLAND REMOVAL
	FOOT	SQ FT	SQ FT	SQ FT
<b>IL 13</b>				
<b>EBL</b>				
LT STA 857+60.00 TO STA 859+88.39		839.2		
RT STA 859+34.43 TO STA 8+30.56 RUSSELL ST.	155.3			
RT STA 859+93.28 TO STA 860+06.07				109.0
LT STA 860+72.78 TO STA 863+11.51		719.8		
LT STA 863+11.51 TO STA 867+26.70			4,941.0	
LT STA 863+11.51 TO STA 867+26.70	415.2			
RT STA 871+26.92 TO STA 871+61.33	67.1			
RT STA 872+00.11 TO STA 872+37.53	67.0			
RT STA 876+43.43 TO STA 876+70.31	48.5			
RT STA 876+93.27 TO STA 880+09.43	404.3			
RT STA 880+33.52 TO STA 883+49.64	411.0			
LT STA 882+80.00 TO STA 883+25.00		225.0		
LT STA 883+99.05 TO STA 884+10.00		62.0		
<b>WBL</b>				
LT STA 859+76.29 TO STA 860+10.65	57.5			
LT STA 860+51.07 TO STA 860+86.42	60.5			
RT STA 863+11.27 TO STA 863+52.00	40.7			
RT STA 867+10.7 TO STA 867+24.70	14.0			
LT STA 871+29.81 TO STA 871+62.25	58.6			
LT STA 872+01.04 TO STA 872+35.38	66.1			
LT STA 876+20.93 TO STA 876+64.53	64.3			
LT STA 877+08.61 TO STA 883+53.73	677.7			
LT STA 883+76.78 TO STA 886+78.98	387.0			
<b>RUSSELL ST.</b>				
RT STA 8+57.77 TO STA 860+85.09 EBL IL 13	114.2			
<b>PROJECT TOTAL</b>				
	3,109	1,846.0	4,941	109

FILE NAME *	USER NAME * levanderbe	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE - CURB &amp; GUTTER, MEDIAN REMOVAL</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pvc_work\pvc\dot\levanderbe\0184451\78	203-ahf-sched.dgn	DRAWN -	REVISED -			331	(1X-1)R-5,RS-3,N-5,TS-4	WILLIAMSON	288	35	
	PLOT SCALE * 1/8"=1'-0"	CHECKED -	REVISED -			CONTRACT NO. 78203					
	PLOT DATE * 9/12/2012	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					