

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	UNION COUNTY	PULASKI COUNTY
				ROADWAY RURAL 90% FEDERAL ; 10% STATE	
CONSTRUCTION TYPE CODE				0004	
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	534	406	128
X0323388	TRAFFIC COUNTER	EACH	1		1
X6311217	TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL)	EACH	2	2	
X6330900	VERTICAL ADJUSTMENT OF GUARDRAIL	FOOT	3,375	3,375	
Z0034105	MATERIAL TRANSFER DEVICE	TON	45,474	34,355	11,119
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	53,845	40,509	13,336
Z0055605	RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT	SQ YD	63,994	46,954	17,040
* 25000200	SEEDING, CLASS 2	ACRE	1.7	1.1	0.6
* 25000350	SEEDING, CLASS 7	ACRE	1.7	1.1	0.6
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	306	198	108
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	153	99	54
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	153	99	54
* 25100115	MULCH, METHOD 2	ACRE	3.4	2.2	1.2
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	3.4	2.2	1.2
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	170	110	60
28100207	STONE RIPRAP, CLASS A4	TON	1,253	835	418
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	11,285	8,536	2,749
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	20,463	15,750	4,713
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	10	7.6	2.4
40600895	CONSTRUCTING TEST STRIP	EACH	3	3	
40600982	HOT-MIX SURFACE REMOVAL - BUTT JOINT ASPHALT	SQ YD	1,371	1,202	169
40600990	TEMPORARY RAMP	SQ YD	77	77	
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	32,650	24,376	8,274
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	9,407	7,217	2,190
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	8,615	6,645	1,970
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	56	56	

* SPECIALTY
ITEM

26 73

FILE NAME =	USER NAME = Stovarrpg	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
of\p\work\p\p\stovarrpg\48289789\70239-shb\tp\sch.dgn		DRAWN -	REVISED -			57	(17-1,91-4,91-4-1,91-3)R-1	UNION/PULASKI	39	7
PLOT SCALE = 1/8" = 100' / in.		CHECKED -	REVISED -		SCALE: _____					
PLOT DATE = 6/16/2012		DATE -	REVISED -		SHEET NO. ___ OF ___ SHEETS					
					STA. _____ TO STA. _____					
										CONTRACT NO. 78289
										[ILLINOIS] FED. AID PROJECT