

PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	PERFORMED PAVEMENT MARKING								REMARKS	
	LINE 6"	LINE 6"	LINE 4"		LINE 8"	LINE 12"	LINE 24"	LETTERS & SYMBOLS		
	SOLID WHITE FOOT	SKIP DASH WHITE FOOT	SOLID WHITE FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT	SOLID WHITE FOOT	SOLID WHITE FOOT	SQ FOOT		
NORTHBOUND										
UNION COUNTY										
2941+25 TO 2982+27		1026	4102	4102						
2982+27 TO 2990+44	1366	205	1416	620		352				
2990+44 TO 2994+56		206	412	412						
2994+56 TO 3003+00		582	1042	1049	205			46.7	ONLY; LT TURN ARROW; EXIT TO; US 51; STRAIGHT ARROW	
3003+00 TO 3008+37		194	537	537				41.3		
3008+37 TO 3011+95		90	358	358						
3011+95 TO 3015+92	GAP SN 091-0004									
3015+92 TO 3020+14		106	422	422						
3020+14 TO 3025+13		125	817	704						
3025+13 TO 3026+41 BK =		32	128	128						
3026+29 AH TO 3039+37		327	1308	1308						
3039+37 TO 3040+83	GAP SN 091-0001									
3040+83 TO 3143+51 BK =		2567	10268	10268						
RAMP A			806	806						
RAMP B			1223	1223			60			
UNION COUNTY SUBTOTALS	1366	5460	22839	21937	205	352	60	88		
PULASKI COUNTY										
0+00 AH TO 66+00.0		1650	6600	6600						
PULASKI COUNTY SUBTOTALS	0	1650	6600	6600	0	0	0	0		
TOTALS	1,366	7,110	29,439	28,537	205	352	60	88		
	8,476		57,976							

NOTE: ALL LETTERS ARE THE 8' SIZE AND ALL SYMBOLS ARE THE LARGE SIZE.