

FAP RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
729	*	VERMILION	298	33
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 36(W,RS-1) & 34Z-2(W,RS)		CONTRACT #90939		

PAVEMENT SCHEDULE

STATION TO STATION	AREA	SUB-BASE GRANULAR MATERIAL, TYPE B, 100MM M3111100 SQ M	AGGREGATE BASE COURSE, TYPE A, 150MM M3511150 SQ M	PORTLAND CEMENT CONCRETE BASE M3540200 SQ M	BITUMINOUS MATERIALS (PRIME COAT)				AGGREGATE (PRIME COAT)	POLYMERIZED HOT-MIX ASPHALT			INCIDENTAL HMA SURFACING M4080500 M TON	PORTLAND CEMENT CONCRETE PAVEMENT 200MM M4200200 SQ M
					1ST APPLICATION	2ND APPLICATION	3RD APPLICATION	4TH APPLICATION	ALL APPLICATIONS	LEVEL BINDER (MM) IL-9.5, F.G., N90	BINDER COURSE, IL-19.0, F.G., N90	SURFACE COURSE, MIX "D", N90		
					LITER	LITER	LITER	LITER	M TON	M TON	M TON	M TON		
93+951.420 93+965.500	253.4	54.7		38.9	74.9	74.9	88.7	88.7	1.40	27.30	98.6	23.0		
93+965.500 94+012.300	937.0	203.9		149.5	278.5	278.5	324.3	324.3	5.17	100.90	365.9	84.1		
94+012.300 94+058.640	1,010.2	220.9		136.2	304.9	304.9	350.3	350.3	5.60	108.70	400.2	90.9		
94+058.640 94+102.240	784.8	172.7		146.1	232.0	232.0	274.7	274.7	4.30	84.40	305.3	71.3		
94+102.240 94+311.650	4,145.9	1,176.5		813.2	1,114.1	1,114.1	1,439.9	1,439.9	21.90	446.10	1,465.6	376.5		
94+311.650 94+349.860	687.8	112.2		105.5	203.3	203.3	240.7	240.7	3.80	74.00	267.5	62.5		
94+349.860 94+630.000	5,042.5	1,198.4		811.4	1,492.2	1,492.2	1,764.9	1,764.9	27.90	542.60	1,961.3	457.9		
94+630.000 94+960.560	5,950.1	1,446.5		915.1	1,772.5	1,772.5	2,082.5	2,082.5	33.00	640.20	1,108.8	540.3		
94+960.560 95+245.620	5,131.1	1,146.4		798.5	1,521.5	1,521.5	1,795.8	1,795.8	28.40	552.10	956.2	465.9		
95+245.620 95+293.710	754.5	167.8		147.4	204.0	204.0	258.3	258.3	3.93	81.20	141.0	67.0		
95+293.710 95+400.000	1,178.2	320.4		122.5	364.1	364.1	375.9	375.9	6.30	126.80	222.5	97.5		
95+400.000 95+420.000	150.4	48.0			54.2	54.2	52.6	52.6	0.97	16.20	33.1	6.8		
95+420.000 95+484.880	473.3	155.7			165.7	165.7	165.7	165.7	1.42	50.90	104.1	43.0		
NICKLAS AVE														
51+009.010 51+029.000	151.6	188.2												151.6
WEST V.A. ENTRANCE														
71+950.000 71+991.000	743.1	861.6												743.1
IOWA STREET														
52+009.000 52+100.000	1,017.7	1,194.6												1,017.7
ILLINOIS STREET														
53+009.010 53+040.000	376.0	425.9												376.0
WEST D.A.C.C. ENTRANCE														
72+959.000 72+990.990	448.5	535.9												467.5
INDIANA AVE														
54+009.010 54+036.000	278.8	336.3												278.8
OHIO STREET														
55+009.010 55+022.000	114.2	146.1												114.2
NEBRASKA STREET														
100+23.757 100+29.511	73.2	89.6												73.2
EAST D.A.C.C. ENTRANCE														
73+980.000 73+991.000	93.1	118.0												93.1
EAST V.A. ENTRANCE														
74+949.531 74+980.222	237.3		237.3		356.0				0.36				43.4	
74+980.222 74+990.993	172.2	199.2												172.2
PENNSYLVANIA AVE														
56+009.010 56+021.500	135.3	163.7												135.3
HOME AVE														
56+971.000 56+990.990	160.3	200.9												160.3
WISCONSIN AVE														
58+009.010 58+035.000	185.6	243.3												185.6
TILLMAN STREET														
58+962.000 58+991.000	215.2	271.8												215.2
MICHIGAN AVE														
60+009.010 60+024.000	141.8	176.8												141.8
MINNESOTA AVE														
61+009.000 61+022.000	128.7	160.6												128.7
NORTH OREGON AVE														
62+009.010 62+050.000	533.0	621.2												533.0
SOUTH OREGON AVE														
62+952.000 62+958.000	42.2		42.2		58.1				0.05				7.1	
62+958.000 62+991.000	299.6	376.1												299.6
NORTH CALIFORNIA AVE														
64+009.010 64+017.530	82.3	106.3												82.3
SOUTH CALIFORNIA AVE														
64+966.000 64+976.000	85.3		85.3		122.3				0.12				14.9	
64+976.000 64+990.590	154.8	192.0												154.8
NORTH KANSAS AVE														
66+009.010 66+026.500	174.8	216.7							113.3					174.8
66+026.500 66+036.500	81.5		81.5						0.11				13.8	
SOUTH KANSAS AVE														
66+978.500 66+990.990	120.3	149.4												120.3
TOTAL		13,398.3	446.3	4,184.3			(ALL APPLICATIONS)	34,642.1	144.73	2851.40	7,430.1	2,386.7	79.2	5,819.1
USE		13,399	447	4,185			(ALL APPLICATIONS)	34,643	145	2852	7,431	2,387	80	5,820

SCHEDULES OF
QUANTITIES

8/17/2012