

COMBINATION CONCRETE CURB AND GUTTER

STATION TO STATION	SIDE	TYPE B			STATION TO STATION	SIDE	TYPE B			STATION TO STATION	SIDE	TYPE B								
		15.30	15.45	15.60			15.30	15.45	15.60			15.30	15.45	15.60						
		M	M	M			M	M	M			M	M	M						
		M6060500	M6060600	M6060700			M6060500	M6060600	M6060700			M6060500	M6060600	M6060700						
93+951.420	93+965.500	RT			94+792.090	94+868.280	LT			94+016.650	54+036.000	LT								
93+951.420	93+986.490	LT			94+868.280	94+877.050	LT			54+021.820	54+036.000	RT		19.35						
93+965.500	94+012.300	RT			94+884.490	94+893.400	LT			OHIO STREET				14.18						
93+986.490	93+993.980	LT			94+893.400	94+960.560	LT			55+015.890	55+022.000	LT		6.11						
94+570.020	94+578.800	LT			94+960.560	94+978.310	LT			55+016.860	55+022.000	RT		5.14						
94+000.220	94+007.510	LT			94+986.730	94+993.980	LT			EAST D.A.C.C. ENTRANCE										
94+007.510	94+066.370	LT			94+993.980	95+005.940	LT			73+985.270	73+980.000	LT	5.27							
94+012.300	94+058.650	RT			94+966.170	94+978.160	RT			73+985.910	73+980.000	RT	5.91							
94+058.650	94+072.650	RT			94+985.390	94+997.380	RT			EAST V.A. ENTRANCE										
94+066.370	94+076.360	LT			94+977.380	95+070.580	RT			74+985.920	74+979.500	LT		6.42						
94+088.270	94+102.270	RT			95+005.940	95+071.040	LT			PENNSYLVANIA AVE										
94+089.050	94+100.960	LT			95+070.580	95+079.570	RT			56+015.230	56+021.500	LT	6.27							
94+100.960	94+205.560	LT			95+087.600	95+096.590	RT			56+016.200	56+021.500	RT	5.30							
94+102.250	94+311.650	RT			95+071.040	95+079.820	LT			HOME AVE										
94+205.560	94+211.160	LT			95+086.290	95+093.700	LT			56+983.990	56+971.000	LT	12.99							
94+222.740	94+231.550	LT			95+093.700	95+172.050	LT			56+983.940	56+971.000	RT		12.94						
94+231.550	94+317.940	LT			95+096.590	95+179.910	RT			WISCONSIN AVE										
94+311.650	94+323.460	RT			95+172.050	95+181.040	LT			58+017.570	58+035.000	LT		17.43						
94+317.940	94+327.700	LT			95+189.070	95+198.070	LT			58+018.460	58+035.000	RT		16.54						
94+335.930	94+349.860	LT			95+179.910	95+188.690	RT			TILLMAN STREET										
94+336.740	94+348.300	RT			95+195.920	95+204.530	RT			58+983.270	58+962.000	LT		21.27						
94+348.300	94+445.090	RT			95+198.070	95+245.610	LT			58+984.000	58+962.000	RT		22.00						
94+349.860	94+434.620	LT			95+204.530	95+245.620	RT			MICHIGAN AVE										
94+434.620	94+443.400	LT			95+245.610	95+293.720	LT			60+015.930	60+024.000	LT		8.07						
94+445.090	94+452.350	RT			95+245.620	95+342.600	RT			60+016.830	60+024.000	RT		7.17						
94+449.730	94+458.640	LT			95+293.720	95+342.600	LT			MINNESOTA AVE										
94+458.630	94+487.550	LT			NICKLAS AVE							61+015.880	61+022.000	LT		6.12				
94+458.960	94+466.100	RT			51+014.910	51+029.000	RT		14.09	61+016.880	61+022.000	RT		5.12						
94+466.100	94+488.790	RT			51+018.600	51+029.000	LT		11.00	NORTH OREGON AVE										
94+487.550	94+495.190	LT			WEST V.A. ENTRANCE							62+023.850	62+050.000	LT		26.15				
94+488.790	94+495.980	RT			71+973.360	71.950.000	LT		23.36	62+039.960	62+050.000	RT		10.04						
94+503.530	94+510.720	RT			71+977.110	71.950.000	RT		27.11	SOUTH OREGON AVE										
94+510.720	94+608.270	RT			IOWA STREET							62+978.470	62+958.000	LT		20.47				
94+514.666	94+522.290	LT			52+018.130	52+032.100	LT		15.11	62+979.510	62+958.000	RT		21.51						
94+522.290	94+552.980	LT			52+023.230	52+032.100	RT		8.14	NORTH CALIFORNIA AVE										
94+552.980	94+561.590	LT			52+032.100	52.053.100	LT		23.26	64+015.900	61+017.530	LT		1.63						
94+578.800	94+660.850	LT			52+032.100	52+053.700	RT		19.96	64+015.450	64+017.530	RT		2.08						
94+608.270	94+617.030	RT			52+053.700	52.097.190	LT		41.35	SOUTH CALIFORNIA AVE										
94+623.480	94+632.280	RT			52+053.700	52+097.140	RT		45.63	64+981.530	64+976.000	LT		5.53						
94+632.780	94+715.430	RT			52+097.190	52+100.000	LT		2.81	64+982.450	64+976.000	RT		6.45						
94+660.850	94+669.840	LT			52+097.140	52+100.000	RT		2.86	NORTH KANSAS AVE										
94+675.670	94+684.670	LT			ILLINOIS ST							66+017.130	66+026.500	LT		8.97				
94+684.670	94+766.930	LT			53+012.570	53+040.000	LT		27.43	66+018.490	66+026.500	RT		8.01						
94+715.430	94+724.320	RT			53+016.440	53+040.000	RT		23.56	SOUTH KANSAS AVE										
94+730.650	94+739.440	RT			WEST D.A.C.C ENTRANCE							66+983.850	66+978.500	LT	5.35					
94+739.440	94+966.170	RT			72+959.000	72+977.211	LT		18.21	66+984.740	66+978.500	RT		6.24						
94+766.970	94+775.750	LT			72+959.000	72+982.56	RT		23.56	TOTAL										
94+783.180	94+792.090	LT										165.18	167.37	3096.66						
											USE					165.2	167.4	3096.7		

EARTHWORK SCHEDULE

LOCATION	DESCRIPTION	1	2	3	4	5
		EARTH EXCAVATION	EARTH EXCAVATION (WIDENING)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		M2020010	M2020050			
FAP 729 (US 136)	LT STA 93+951.42 TO STA 95+420.00	2400	504	2178	673	+1505
FAP 729 (US 136)	RT STA 93+951.42 TO STA 95+420.00	1952	639	1943	377	+1567
FAP 729 (US 136)	RT/LT STA 95+420.00 TO STA 95+484.880	438	0	329	0	+329
CULVERT OUTLET	CULVERT STA 99+934.68 TO STA 99+980.86	172	0	129	0	+129
TOTALS		4962	1143	4579	1050	+3530

COLUMN 3 = (COLUMN 1 + COLUMN 2) * 0.75
 COLUMN 5 = COLUMN 3 - COLUMN 4

NOTE: ALL SIDESTREETS AND ENTRANCES ARE INCLUDED WITHIN THE APPROPRIATE STATION RANGE

SCHEDULES OF QUANTITIES

8/17/2012