

PAVEMENT PATCHING SCHEDULE (CONTD)

STATION	DIRECTION	LANE	LENGTH	WIDTH	DEPTH OF PATCH	PARTIAL DEPTH REMOVAL 75 mm MX033842 (sq m)	PARTIAL DEPTH PATCHING MX033843 (metric tons)
			(m)	(m)	(mm)		
94+647.00	EB	DRIVE / PASS	1.2	6.70	75	8.0	1.44
94+647.00	WB	DRIVE/PASS/CTR.TURN	1.2	9.14	75	11.0	1.97
94+701.00	EB	DRIVE / PASS	1.2	6.70	75	8.0	1.44
94+701.00	WB	DRIVE/PASS/CTR.TURN	1.2	9.14	75	11.0	1.97
94+730.00	EB	DRIVE / PASS	1.2	6.70	75	8.0	1.44
94+730.00	CTR.	CTR. TURN	1.2	1.80	75	2.2	0.39
94+776.00	EB	DRIVE / PASS	1.2	6.70	75	8.0	1.44
94+776.00	WB	DRIVE/PASS/CTR.TURN	1.2	9.14	75	11.0	1.97
94+812.00	EB	DRIVE / PASS	1.2	6.70	75	8.0	1.44
94+812.00	WB	DRIVE/PASS/CTR.TURN	1.2	9.14	75	11.0	1.97
94+856.00	EB	DRIVE / PASS	1.2	6.70	75	8.0	1.44
94+856.00	CTR.	CTR. TURN	1.2	1.80	75	2.2	0.39
94+880.00	EB	DRIVE / PASS	1.2	6.70	75	8.0	1.44
94+880.00	CTR.	CTR. TURN	1.2	1.80	75	2.2	0.39
94+930.00	EB	DRIVE / PASS	1.2	6.70	75	8.0	1.44
94+930.00	WB	DRIVE/PASS/CTR.TURN	1.2	9.14	75	11.0	1.97
94+960.00	EB	DRIVE / PASS	1.2	6.70	75	8.0	1.44
94+960.00	WB	DRIVE/PASS/CTR.TURN	1.2	9.14	75	11.0	1.97
95+021.00	EB	DRIVE / PASS	1.2	6.70	75	8.0	1.44
95+021.00	WB	DRIVE/PASS/CTR.TURN	1.2	9.14	75	11.0	1.97
95+075.00	EB	DRIVE / PASS	1.2	6.70	75	8.0	1.44
95+075.00	WB	DRIVE/PASS/CTR.TURN	1.2	9.14	75	11.0	1.97
95+097.00	EB	DRIVE / PASS	1.2	6.70	75	8.0	1.44
95+097.00	CTR.	CTR. TURN	1.2	1.80	75	2.2	0.39
95+130.00	EB	DRIVE / PASS	1.2	6.70	75	8.0	1.44
95+130.00	WB	DRIVE/PASS/CTR.TURN	1.2	9.14	75	11.0	1.97
95+186.00	EB	DRIVE / PASS	1.2	6.70	75	8.0	1.44
95+186.00	CTR.	CTR. TURN	1.2	1.80	75	2.2	0.39
95+234.00	EB	DRIVE / PASS	1.2	6.70	75	8.0	1.44
95+234.00	WB	DRIVE/PASS/CTR.TURN	1.2	9.14	75	11.0	1.97
SUB TOTALS						241.1 (sq m)	43.2 (metric tons)

PAVEMENT PATCHING SCHEDULE (CONT.)

STATION	DIRECTION	LANE	LENGTH	WIDTH	DEPTH OF PATCH	PARTIAL DEPTH REMOVAL 75 mm MX033842 (sq m)	PARTIAL DEPTH PATCHING MX033843 (metric tons)
			(m)	(m)	(mm)		
95+269.00	EB	DRIVE	1.2	7.62	75	9.1	1.64
95+269.00	WB	DRIVE	1.2	7.62	75	9.1	1.64
95+305.00	EB	DRIVE	1.2	7.62	75	9.1	1.64
95+305.00	WB	DRIVE	1.2	7.62	75	9.1	1.64
95+335.00	EB	DRIVE	1.2	7.62	75	9.1	1.64
95+335.00	WB	DRIVE	1.2	7.62	75	9.1	1.64
SUB TOTALS						54.9 (sq m)	9.8 (metric tons)

TOTALS	PARTIAL DEPTH REMOVAL 75 mm MX033842 (sq m)	PARTIAL DEPTH PATCHING MX033843 (metric tons)
295.9	295.9	53.0
USE	296.0	53.0

TEMPORARY ACCESS

STATION	SIDE	TEMPORARY ACCESS (PRIVATE ENTRANCE) X4021000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE) X4022000
		EACH	EACH
93+966.500	LT		1
94+018.300	LT		1
94+037.000	LT	1	
94+045.400	LT		1
94+181.100	LT		1
94+276.900	LT		1
94+293.700	LT	1	
94+360.500	LT		1
94+380.600	LT		1
94+402.600	LT	1	
94+420.700	LT	1	
94+482.800	LT		1
94+513.300	LT		1
94+604.100	LT	1	
94+621.500	LT		1
94+636.400	LT	1	
94+645.100	RT	1	
94+676.900	RT	1	
94+694.700	LT	1	
94+708.100	LT	1	
94+722.900	LT	1	
94+752.600	RT	1	
94+782.800	RT		1
94+827.400	RT	1	
94+903.600	RT		1
94+942.500	LT	1	
95+003.880	RT	1	
95+032.000	RT	1	
95+032.200	LT	1	
95+044.900	RT	1	
95+047.500	LT	1	
95+061.100	RT	1	
95+104.100	LT	1	
95+134.100	LT	1	
95+140.600	RT	1	
95+158.900	LT	1	
95+164.400	RT		1
95+237.500	LT		1
95+266.000	RT	1	
95+267.100	LT	1	
95+285.500	RT	1	
95+334.200	RT	1	
95+454.300	RT	1	
NICKLAS AVE			
51+020.100	LT		1
IOWA STREET			
52+062.600	LT		1
52+062.600	RT		1
52+085.800	RT	1	
ILLINOIS STREET			
53+028.800	RT		1
WEST D.A.C.C. ENTRANCE			
72+964.200	RT		1
INDIANA AVE			
54+027.500	RT		1
WISCONSIN AVE			
58+028.300	LT	1	
TILLMAN STREET			
58+959.700	RT	1	
NORTH OREGON AVE			
62+041.800	LT	1	
SOUTH OREGON AVE			
62+968.000	LT	1	
62+966.600	RT	1	
TOTAL		35	20
USE		35	20

M4402000 - PAVEMENT REMOVAL

STATION TO STATION		AREA SQ M
93+951.420	93+9650790	13.1
WEST V.A. ENTRANCE		
71+950.000	71,992.880	767.1
IOWA STREET		
52+012.220	52+100.000	790.2
ILLINOIS STREET		
53+007.190	53+040.000	396.1
WEST D.A.C.C. ENTRANCE		
72+975.700	72+993.470	260.6
INDIANA AVE		
54+007.130	54+036.000	250.6
OHIO AVE		
55+006.760	55+022.000	128.8
NEBRASKA STREET		
100+23.756	100+39.542	149.4
EAST D.A.C.C. ENTRANCE		
73+980.000	73+992.650	85.5
PENNSYLVANIA AVE		
56+007.920	56+021.500	139.4
WISCONSIN AVE		
58+007.260	58+035.000	191.0
TILLMAN STREET		
58+962.000	58+992.690	216.4
MICHIGAN AVE		
60+007.280	60.024.000	136.8
MINNESOTA AVE		
61+007.240	61+022.000	125.8
NORTH OREGON AVE		
62+007.270	62+050.280	379.2
SOUTH OREGON AVE		
62+979.860	62+992.760	103.4
NORTH CALIFORNIA AVE		
64+007.330	64+017.530	85.3
SOUTH CALIFORNIA AVE		
64+998.020	64+992.560	42.4
NORTH KANSAS AVE		
66+007.350	66+012.430	49.3
SOUTH KANSAS AVE		
66+978.500	66+992.490	145.4
TOTAL		4,455.9
USE		4,456

SCHEDULES OF QUANTITIES