FAP RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
729	•	VERMILION	298	43
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• 36(W,RS-1) & 34Z-2(W,RS)			CONTRACT 90939	

STORM SEWER SCHEDULE (CONT'D)

STR #	STATION	TYPE	STD # SEE LEGEND	STORM SEWER																MANHOLES, TYPE A									INLETS									VANE DRAIN	TRENCH BACKFILL
				CLASS A										CLASS B			WATER MAIN REQUIREMENTS				1.2m DIA			1.5m DIA			1.8m DIA			TYPE A					TYPE B					
				RUBBER GASKET																																				
				TYPE 1			TYPE 2							TYPE 1																										
				300 mm	375 mm	450 mm	300 mm	375 mm	450 mm	600 mm	750	1050 mm	1200 mm	100m m	250 mm	375 mm	300 mm	375 mm	600 mm	750 mm	FRAME AND GRATE TYPE																			
																					1-C	3	3V	1-C	3	3V	1-C	3	SPC.	3	3V	8	9	11	1-C	3	3V	9	11		
				METER																EACH																				METER	CU M
35	94+167.00	INLET	A.H																												1										
		SS														19.0																									2.0
		VANE	M																																					9.7	
		SS								52.4																															136.0
36	94+220.30	MH	C.E.F																					1																	
		SS					6.7																																		14.0
37	94+220.30	MH	C.E.F																		1																				
		SS		10.4																																					5.0
38	94+223.00	INLET	A.H																												1										
ILLINOIS ST.																																									
		SS			6.7																																				5.0
39	53+018.26	MH	C.E.F																		1																				
		SS		1.8																																					1.0
40	53+016.88	INLET	B.E.K																																				1		
		SS		1.2																																					1.0
41	53+014.50	INLET	A.G																												1										
		SS		8.5																																					5.0
42	53+016.88	INLET	B.E.K																																				1		
		SS															1.8																								1.0
43	53+020.00	INLET	A.K																																1						
44	94+226.48	INLET	B.E.F																																	1					
		SS							43.9																																100.0
45	94+265.00	MH	C.H																				1																		
		SS					6.7																																		14.0
46	94+265.00	MH	C.E.F																		1																				
		SS		14.0																																					7.0
47	94+265.00	INLET	A.H																													1									
		SS							70.7																																161.0
48	94+337.00	MH	C.F																		1																				
		SS					7.3																																		15.0
49	94+337.00	MH	C.F																		1																				
		SS		15.2																																					26.0
WEST DACC ENT																																									
50	72+985.50	INLET	B.E.G																																		1				
		SS		2.4																																					2.0
51	72+982.43	INLET	B.E.G																																		1				
		SS		17.7																																					11.0
52	72+983.02	INLET	A.G.																											1											

8/17/2012

SCHEDULES OF QUANTITIES

c:\pw_work\pwidot\cearlockjd\d0313241\D590939-sht-schedule.dgn