FAP RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
729	*	VERMILION	298	45
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* 36(W,RS-1) & 34Z-2(W,RS) CONTRACT 90939

STORM SEWER SCHEDULE (CONT'D)

STR #	STATION	TYPE	STD # SEE LEGEND	STORM SEWER																	MANHOLES, TYPE A									INLETS										VANE DRAIN	TRENCH BACKFILL
				CLASS A RUBBER GASKET										CLASS B			WATER MAIN REQUIREMENTS				1.2m DIA			1.5m DIA			1.8m DIA			TYPE A					TYPE B						
				TYPE 1			TYPE 2							TYPE 1																											
				300 mm	375 mm	450 mm	300 mm	375 mm	450 mm	600 mm	750	1050 mm	1200 mm	100m m	250 mm	375 mm	300 mm	375 mm	600 mm	750 mm	FRAME AND GRATE TYPE																				
																					1-C	3	3V	1-C	3	3V	1-C	3	SPC.	3	3V	8	9	11	1-C	3	3V	9	11		
				METER																	EACH																			METER	CU M
71	56+018.54	INLET	A.K																															1							
		SS						23.2																																	51.0
72	94+595.00	MH	C.E.H																				1																		
		SS						7.3																																	15.0
73	94+595.00	MH	C.E.F																		1																				
		SS		11.6																																					6.0
74	94+590.00	INLET	B.E.H																																	1					
		SS		29.9																																					7.0
75	94+560.00	INLET	A.H																												1										
		SS						32.9																																	84.0
76	94+629.00	MH	C.E.H																				1																		
		SS					25.6																																		56.0
HOME AVE																																									
77	56+983.61	MH	C.E.G																			1																			
		SS															2.4																								1.0
78	56+980.50	INLET	A.G																											1											
		SS		6.7																																					3.0
79	56+983.61	INLET	B.E.G																																	1					
		SS		2.4																																					1.0
80	56+986.20	INLET	A.G																											1											
81	94+620.75	MH	C.E.F																		1																				
		SS							47.6																																128.0
82	94+677.50	MH	C.E.F																					1																	
WISCONSIN AVE																																									
		SS		7.9																																					5.0
83	58+018.47	MH	C.E.G																			1																			
		SS		2.4																																					1.0
84	58+021.50	INLET	A.G																											1											
		SS		6.7																																					3.0
85	58+017.57	INLET	B.E.G																																	1					
		SS															2.4																								1.0
86	58+014.70	INLET	A.G																											1											
87	94+678.69	MH	C.F																		1																				
		SS		20.1																																					8.0
88	94+685.50	INLET	A.H																												1										
		SS								53.0																															156.0
89	94+731.50	MH	C.E.H																							1															

8/17/2012

c:\pw_work\pwidot\cearlockjd\d0313241\D590939-sht-schedule.dgn

SCHEDULES OF QUANTITIES