

INDEX OF SHEETS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	INDEX OF SHEETS, GENERAL NOTES, LOCATION DESCRIPTION
3	SUMMARY OF QUANTITIES
4	LOCATION MAP
5-7	EXISTING STRUCTURE PLANS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 7:

000001-06	STANDARD SYMBOLS, ABBREVIATIONS, & PATTERNS
701001-02	OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY
701006-05	OFF-ROAD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
701201-04	LANE CLOSURE, 2L, 2W, FOR SPEEDS >= 45 MPH
701901-07	TRAFFIC CONTROL DEVICES

GENERAL NOTES

THE PROPOSED PROJECT IS LOCATED AT STRUCTURE NUMBER 018-0026 ON ILLINOIS ROUTE 130 LOCATED 1.5 MILES SOUTH OF US ROUTE 40 IN CUMBERLAND COUNTY IN DISTRICT 7.

THE WORK INCLUDED IN THIS SECTION CONSISTS OF CLEANING AND PAINTING THE BRIDGE AS SPECIFIED IN THE PLANS AND SPECIAL PROVISIONS.

THE STRUCTURAL STEEL SHALL BE CLEANED AND PAINTED AS SPECIFIED IN THE PLANS AND THE SPECIAL PROVISIONS.

ALL DECK DRAINS SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1 - OZ/E/U. ANY DAMAGE CAUSED BY THE CONTRACTOR SHALL BE REPAIRED AT THEIR OWN EXPENSE AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

ONLY STRUCTURAL STEEL IS TO BE PAINTED. ALL OTHER SURFACES WILL BE PROTECTED FROM BEING PAINTED. ALL PAINT AND OVERSPRAY WILL BE REMOVED AT THE CONTRACTOR'S EXPENSE.

THE SSPC QP1 AND QP2 PAINTING CONTRACTOR CERTIFICATION WILL BE REQUIRED FOR THIS PROJECT.

LOCATION

BRIDGE # 1
 ROUTE: FAP 116
 MARKED: ILL 130
 SECTION: 113VBR
 STATION: 498+60.60
 STRUCTURE NUMBER: 018-0026

TYPE OF BRIDGES: WIDE FLANGE I BEAMS-3 SPANS - 8 BEAMS
 LOCATION: 1.5 MILES SOUTH OF US ROUTE 40
 FEATURE CARRIED/SPANNED: ILLINOIS ROUTE 130 OVER THE CSXT RAILROAD

COLOR OF THE FINISH COAT SHALL BE GREEN, MUNSELL 10B 3/6.

CLEANING AND PAINTING OF THE EXISTING STRUCTURAL STEEL SHALL BE AS SPECIFIED IN THE SPECIAL PROVISION FOR "CLEANING AND PAINTING EXISTING STEEL STRUCTURES". ALL STRUCTURAL STEEL, INCLUDING ALL BEAMS, BEARINGS, AND DIAPHRAGMS, SHALL BE CLEANED BY SSPC-SP10-NEAR WHITE METAL BLAST CLEANING. THIS STRUCTURE CONTAINS LEAD PAINT. 1

THE DESIGNATED AREAS CLEANED PER NEAR WHITE METAL BLAST CLEANING - SSPC-SP10 SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1 - OZ/E/U.

TWO AIR MONITORS WILL BE REQUIRED AT THIS LOCATION.

1 Rev. 10-24-18

MODEL: Default
 FILE NAME: P:\1108\BARDNET\TEC\Illinois.gov\PWIDOT\Documents\DOT Offices\District 7\Projects\17876\CADD\data\CAD\sheet\ID774876-116-genote.dgn

USER NAME = steffenmk	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 8/16/2018	DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**INDEX OF SHEETS, GENERAL NOTES
 & LOCATION DESCRIPTION**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
116	D7 BRIDGE PAINTING 2019-2	CUMBERLAND	7	2
CONTRACT NO. 74876				
ILLINOIS FED. AID PROJECT				