



Traverse Layout Data

SPECIAL NOTE:
 CONSTRUCTION LIMITS ARE WITHIN THE METROLINK R.R. RIGHT-OF-WAY SO CONTRACTOR IS RESPONSIBLE TO COMPLY WITH INSURANCE REQUIREMENTS SPECIFIED IN ARTICLE 107.11 OF THE SPECIAL PROVISIONS.

Construction Limits	
Northing	Easting
A 693,150	Edge of Dutch Hollow Rd.
B 692,950	2,335,035
C 692,800	2,335,100
D 692,650	Edge of Dutch Hollow Rd.

- 400' --- EXISTING CONTOUR
- 450 --- PROPOSED CONTOUR
- - - - - CONSTRUCTION LIMITS
- ==== EDGE OF ROAD
- ~~~~ TREELINE
- - - - - EDGE OF WATER
- ⊕ SURVEY CONTROL POINT

Legend

Excelsior Mine

N

0 50 100
SCALE IN FEET

**State of Illinois
 Department of Natural Resources**

**Crystal Mine Group
 Reclamation Project
 AML-GRaE-0607
 Randolph, St. Clair and
 Clinton Counties**

Drawn By: M-LF
 Checked By: _____
 Date: 10/17/2007

**Existing & Proposed
 Conditions
 Sheet
 4 of 9**