

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE I000-2A			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	16	16			
40600300	AGGREGATE (PRIME COAT)	TON	81	81			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	12	12			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	364	364			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	53	53			
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4630	4630			
44000150	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	40699	40699			
44002210	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/2"	SQ YD	376	376			
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	276	276			
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	100	100			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
67100100	MOBILIZATION	L SUM	1	1			
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4360	4360			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	472	472			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	24355	24355			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1594	1594			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2158	2158			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	420	420			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	252	252			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE I000-2A			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	472	472			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24355	24355			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1594	1594			
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2158	2158			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	420	420			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	252	252			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	510	510			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	510	510			
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1			
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	780	780			
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	2	2			
* 88600100	DETECTOR LOOP, TYPE I	FOOT	145	145			
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	345	345			
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	51.4	51.4			
<del>X4067107</del>	<del>POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL 4.76, N50</del>	<del>TON</del>	<del>1603</del>	<del>1603</del>			
XX003560	CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	50	50			

9/4/2007 9:40:00 AM C:\p06\contract\60c38\070107\design\enr.dgn

• SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
U.S. 30  
SUMMARY OF QUANTITIES

PLOT DATE: 9/4/2007