

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2678	N-7-5-I-1	COOK	18	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 60C45

SUMMARY OF QUANTITIES

*URBAN
100% STATE*

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT		S.N. 016-0678 FUNDS
				SFTY-2A
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ. YD	1,893	1,893
50157300	PROTECTIVE SHIELD	SQ. YD	1,460	1,460
50300260	BRIDGE DECK GROOVING	SQ. YD	1,776	1,776
67100100	MOBILIZATION	L. SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L. SUM	1	1
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	6,830	6,830
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT	2,254	2,254
*78005110	EPOXY PAVEMENT MARKING-LINE 4"	FOOT	2,585	2,585
*78005140	EPOXY PAVEMENT MARKING-LINE 8"	FOOT	400	400
*78005150	EPOXY PAVEMENT MARKING-LINE 12"	FOOT	120	120
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	16	16
78300100	PAVEMENT MARKING REMOVAL	SQ. FT.	777	777
78300200	RAISED REFLECTIVE PAVEMENT MARKING REMOVAL	EACH	16	16
X0320887	POLYMER CONCRETE	CU. FT.	4.0	4.0
X0322933	SILICONE JOINT SEALER, 2.5"	FOOT	44	44
X0322489	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ. YD.	1,893	1,893
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ. FT.	48.0	48.0
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L. SUM	1	1
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ. YD.	1,893	1,893
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ. YD.	11	11

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
F.A.U. RTE. 2678 / ELMHURST ROAD

SCALE: NONE
DATE: JULY 25, 2007

DRAWN BY: F.M.
CHECKED BY: B.N.S.

CHRISTIAN-ROGE & ASSOC., INC.
CHICAGO ILLINOIS