



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

November 6, 2007

SUBJECT: FAP Route 595 (IL 5)  
Project ACNHF-0595 (031)  
Section 5HBR  
Rock Island County  
Contract No. 64931  
Item No. 94, November 16, 2007 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised sheets 1, 2, 8 and 84 of the Plans.
2. Added sheets 83A and 83B to the Plans.
3. Revised pages 1 and 9 of the Schedule of Prices.
4. Revised page ii of the Table of Contents to the Special Provisions.
5. Added page 86 and 87 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm  
Interim Bureau Chief  
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' with a small 'P.E.' to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: George F. Ryan, Region 2, District 2; Roger Driskell; Estimates

TBW:RS:jc



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 64931

State Job # - C-92-145-06  
 PPS NBR - 2-16410-0000  
 County Name - ROCK ISLAND- -  
 Code - 161 - -  
 District - 2 - -  
 Section Number - 5HBR

Project Number  
 ACNHF-0595/031/

Route  
 FAP 595

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
78008210	POLYUREA PM T1 LN 4	FOOT	16,309.000					
78008240	POLYUREA PM T1 LN 8	FOOT	2,445.000					
78200410	GUARDRAIL MKR TYPE A	EACH	20.000					
78200520	BAR WALL MKR TYPE B	EACH	114.000					
78201000	TERMINAL MARKER - DA	EACH	4.000					
78300100	PAVT MARKING REMOVAL	SQ FT	1,912.000					
* 81020500	CON P 2 IM	FOOT	128.000					
* 81100600	CON AT ST 2 GALVS	FOOT	20.000					
81200230	CON EMB STR 2 PVC	FOOT	185.000					
* 81603035	UD 2#6 #6G XLPUSE 1	FOOT	486.000					
* 81900200	TR & BKFIL F ELECT WK	FOOT	237.000					
* 83600310	LIGHT POLE FDN 30D SP	FOOT	6.500					
* 89502385	REMOV EX CONC FDN	EACH	1.000					
			* REVISED : NOVEMBER 6, 2007					

PLANTING WOODY PLANTS (BDE) ..... 51  
PLASTIC BLOCKOUTS FOR GUARDRAIL (BDE) ..... 52  
POLYUREA PAVEMENT MARKING (BDE) ..... 52  
PRECAST CONCRETE HANDLING HOLES (BDE) ..... 59  
RECLAIMED ASPHALT PAVEMENT (RAP) (BDE) ..... 60  
REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) ..... 66  
REINFORCEMENT BARS (BDE) ..... 66  
SEEDING (BDE) ..... 68  
SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BDE)..... 69  
SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)..... 73  
STEEL PLATE BEAM GUARDRAIL (BDE) ..... 74  
STONE GRADATION TESTING (BDE)..... 75  
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) ..... 75  
TEMPORARY EROSION CONTROL (BDE) ..... 75  
TRAINING SPECIAL PROVISIONS ..... 76  
WATER BLASTER WITH VACUUM RECOVERY (BDE)..... 78  
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID) ..... 79  
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) ..... 82  
LIGHT POLE FOUNDATION, 30" DIAMETER, (SPECIAL) ..... 86  
MAINTENANCE OF EXISTING LIGHTING SYSTEM COMPLETE ..... 86  
REMOVE AND REINSTALL LIGHTING UNIT ..... 86

Revised 11/06/2007

### **LIGHT POLE FOUNDATION, 30" DIAMETER, (SPECIAL)**

This work shall be done in accordance with Section 836 of the Standard Specifications insofar as applicable and as detailed on the Plans.

The conduit used in the foundation shall be PVC conduit as detailed on the Plans.

Basis of Payment. This work will be paid for at the contract unit price per FOOT for LIGHT POLE FOUNDATION, 30" DIAMETER, (SPECIAL), which price shall be payment in full for all labor, equipment, materials, and incidental expenses as necessary to complete the work as specified.

### **MAINTENANCE OF EXISTING LIGHTING SYSTEM COMPLETE**

This work consists of locating all conduit and wiring and maintaining the existing lighting system throughout the various stages of construction until the permanent power distribution is completed to the new pole light on the west side of IL 5 on IL 92 and the existing lights within this lighting system. The existing lighting system includes three circuits as shown on the plans. It shall also be the contractor's responsibility to provide any required temporary power feeds to maintain the existing lighting system during the bridge deck replacement. Therefore, some type of temporary power feed must be provided during various stages of construction. This work shall conform to Section 801 of the "Standard Specifications for Road and Bridge Construction" and shall be subject to review and approval by the District 2 Bureau of Operations.

This item shall be paid for at the contract unit price lump sum for MAINTENANCE OF EXISTING LIGHTING SYSTEM COMPLETE, which price shall be payment in full for furnishing the labor and equipment as described above.

### **REMOVE AND REINSTALL LIGHTING UNIT**

This work shall consist of removing an existing light pole with luminaire and reinstalling on the new light pole foundation at the location determined by the Resident Engineer.

The Contractor shall remove the existing lighting unit as indicated on the plans, protect the existing foundation and wiring, keep the existing lighting system operational and reinstalling the lighting unit on the proposed foundation, making all the necessary connections to place the units back into operation.

The Contractor is responsible for providing a secure place for storage while area is under construction.

The Contractor shall be responsible for replacing any damaged components during the removal, storage or reinstallation of the units.

Added 11/06/2007

FAP 595 (IL 5/IL 92)  
Project ACNHF-0595 (031)  
Section 5HBR  
Rock Island County  
Contract #64931

This work will be paid for at the contract unit each for REMOVE AND REINSTALL LIGHTING UNIT, which price shall be payment in full for removing and reinstalling the lighting unit on the proposed foundation in accordance with the requirements of Section 836 and 821 of the "Standard Specifications for Road and Bridge Construction".

Added 11/06/2007