CONTRACT NO. 64931

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*595	5HBR	ROCKISLAND	139	19
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*(IL 5)

SCHEDULE OF QUANTITIES

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION			OFFSET	REMARKS
250	618+59.0	TO	621+34.0		STAGE 3 EXISTING BARRIER
450	625+62.2	TO	630+37.2		STAGE 3 EXISTING BARRIER
2050	610+18.1	TO	630+37.2		STAGE 4 FROM STAGE 3
750	619+29.6	TO	626+79.0		STAGE 4 FROM STAGE 3
3500	SUBTOTAL				
	IL 84				
350	135+92.8	TO	139+42.9		STAGE 4A FROM 3B
300	137+28.2	TO	140+28.2		STAGE 4A FROM 3B
350	135+80.1	TO	139+30.1		STAGE 3B FROM 3A
300	137+05.3	TO	140+05.3		STAGE 3B FROM 3A
350	135+80.1	TO	139+30.1		STAGE 4B FROM 4A
350	137+05.3	TO	140+55.3		STAGE 4B FROM 4A
2000	SUBTOTAL				
5500	**TOTAL**				

78008210 POLYUREA PAVEMENT MARKING, TYPE I - LINE 4"

FOOT	LOCATION			OFFSET	REMARKS
	IL 5/IL92				
5476	604+70.0	TO	632+08.2	LT & RT	YELLOW CENTERLINE
5476	604+70.4	TO	632+08.2	LT & RT	WHITE EDGELINES
1369	604+70.4	TO	632+08.2	LT & RT	WHITE SKIPDASH
12320	SUBTOTAL				
	RAMP CA				
157	60+42.7	TO	66+69.6	RT	WHITE SKIPDASH
250	52+50.0	TO	55+00.0	LT	YELLOW EDGELINE
543	55+00.0	TO	60+42.7	LT	WHITE EDGELINES
	RAMP AD				
1002	9+92.6	TO	19+94.2	RT	WHITE EDGELINES
134	9+92.6	TO	15+29.8	LT	WHITE SKIPDASH
167	18+27.5	TO	19+94.2	LT	YELLOW EDGELINE
2252	SUBTOTAL				
	IL 84				
451	135+38.6	TO	139+89.9	RT	WHITE EDGELINES
54	136+42.5	TO	138+57.5	LT	WHITE SKIPDASH
174	136+42.5	TO	139+89.9	LT & RT	WHITE SKIPDASH
363	136+42.5	TO	140+05.9	LT	WHITE EDGELINES
695	136+42.5	TO	139+89.9	LT & RT	YELLOW EDGELINE
1737	SUBTOTAL				
16309	**TOTAL**				

78008240 POLYUREA PAVEMENT MARKING, TYPE I - LINE 8"

FOOT	LOCATION			OFFSET	REMARKS
	RAMP CA				
1585	52+50.0	TO	60+42.7	RT	WHITE EDGELINE
	RAMP AD				
595	15+29.8	TO	18+27.5	LT	WHITE EDGELINE
	RAMP AD TO CA				
264	138+57.7	TO	139+89.8	LT	WHITE EDGELINE
2445	**TOTAL**				

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION			OFFSET	REMARKS
	IL 5/ IL 92				
4	621+47.5	TO	622+29.1	LT	MONODIRECTIONAL SILVER
4	621+92.9	TO	622+86.6	RT	MONODIRECTIONAL SILVER
4	624+35.6	TO	625+29.3	LT	MONODIRECTIONAL SILVER
12	SUBTOTAL				
	IL 84				
4	135+72.6	TO	138+35.1	RT	MONODIRECTIONAL SILVER
4	138+21.7	TO	140+71.7	LT	MONODIRECTIONAL SILVER
8					
20	**TOTAL**				

78200520 BARRIER WALL MARKERS, TYPE B

EACH	LOCATION			OFFSET	REMARKS
104	604+70.4	TO	630+37.2		MONODIRECTIONAL AMBER
5	622+29.1	TO	624+35.6	LT	MONODIRECTIONAL CLEAR
5	622+86.6	TO	624+83.4	RT	MONODIRECTIONAL CLEAR
114	**TOTAL**				

78201000 TERMINAL MARKER - DIRECT APPLIED

EACH	LOCATION	OFFSET	REMARKS
	IL 5/IL 92		
1	621+92.9	RT	
1	625+29.3	LT	
2	SUBTOTAL		
1	135+72.6	RT	
1	140+71.7	LT	
2	SUBTOTAL		
4	**TOTAL**		

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION			OFFSET	REMARKS
	IL 5 / IL 92				
	STAGE 3				
167	615+80.0	TO	620+80.0	RT	
391	615+80.0	TO	627+53.0	RT	
52	618+25.0	TO	619+80.0	LT	
270	619+50.0	TO	627+60.0	LT	
92	627+60.0	TO	630+37.2	LT	
	STAGE 4				
100	614+00.0	TO	617+00.0	LT	
129	616+62.0	TO	620+48.0	LT	
350	617+00.0	TO	627+50.0	LT	
300	619+00.0	TO	628+00.0	LT	
61	TEMP RAMP				
1912	**TOTAL**				

X0300136 BRIDGE APPROACH SHOULDER REMOVAL

SQ YD	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
105	621+00.0	TO	622+05.3	LT	
144	621+00.0	TO	622+60.6	RT	
87	624+38.1	TO	625+58.2	LT	
59	624+83.5	TO	625+58.2	RT	
396	**TOTAL**				

X0320547 REMOVE AND REINSTALL END SECTION

EACH	LOCATION	OFFSET	REMARKS
	IL 5/IL 92		
1	614+09.0	64' RT	
1	**TOTAL**		

X0712400 TEMPORARY PAVEMENT

SQ YD	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
2	611+09.5				3'X4.3' @ DRAINAGE STRUCTURES
2	614+09.6				3'X4.3' @ DRAINAGE STRUCTURES
2	617+10.0				3'X4.3' @ DRAINAGE STRUCTURES
5	**SUBTOTAL**				
	RAMP AD				
275	18+26.0	TO	19+70.0		
	RAMP CA				
479	52+50.0	TO	MAINLINE		
754	**SUBTOTAL**				
758	**TOTAL**				

X0919000 TEMPORARY PAVEMENT REMOVAL

SQ YD	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
2	611+09.5				3'X4.3' @ DRAINAGE STRUCTURES
2	614+09.6				3'X4.3' @ DRAINAGE STRUCTURES
2	617+10.0				3'X4.3' @ DRAINAGE STRUCTURES
5	**SUBTOTAL**				
	RAMP AD				
275	18+26.0	TO	19+70.0		
	RAMP CA				
479	52+50.0	TO	MAINLINE		
754	**SUBTOTAL**				
758	**TOTAL**				

X6060500 CORRUGATED MEDIAN REMOVAL

SQ FT	LOCATION			OFFSET	REMARKS
	IL 5/IL 92				
338	617+82.8	TO	618+32.6		
338	**TOTAL**				

Z0029999 IMPACT ATTENUATORS REMOVAL

EACH	LOCATION	OFFSET	REMARKS
	IL 5/IL 92		
1	604+71.5		
1	618+58.3		
2	**TOTAL**		

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = Thu Sep 28 14:28:17 2007
FILE NAME = c:\pro-jects\p285203\d85203sp1.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = eckstallcpg