

SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	5HBR	ROCKISLAND	139	19A

STA.	TO STA.

FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT

*(IL 5)

Z0030020 IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2				REMARKS
EACH	LOCATION	OFFSET		
	IL 84			
1	137+62.9			
1	138+69.4			
<u>2</u>	TOTAL			

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3				REMARKS
EACH	LOCATION	OFFSET		
	IL 5/IL 92			
1	627+29.0	4.53' LT		STAGE 3
<u>1</u>	SUBTOTAL			
	IL 84			
1	135+92.8	30.6' RT		STAGE 3A
1	140+28.2	28.6' LT		STAGE 3A
1	135+80.1	21.2' RT		STAGE 3B ABSORB 350 REQUIRED
1	140+55.3	21.2' LT		STAGE 3B ABSORB 350 REQUIRED
<u>4</u>	SUBTOTAL			
<u>5</u>	TOTAL			

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3				REMARKS
EACH	LOCATION	OFFSET		
	IL 5/IL 92			
1	619+29.6	4.24' RT		STAGE 4
	IL 84			
1	135+92.8	30.6' RT		STAGE 4A FROM 3A
1	140+28.2	28.6' LT		STAGE 4A FROM 3A
1	135+80.1	21.2' RT		STAGE 4B FROM 3B
1	140+55.3	21.2' RT		STAGE 4B FROM 3B
<u>4</u>	SUBTOTAL			
<u>5</u>	TOTAL			

Z0065752 SLOTTED DRAIN WITH 6" SLOT				REMARKS
FOOT	LOCATION	OFFSET		
	IL 5/IL 92			
100	621+34.6	LT	622+34.6	
100	621+82.4	RT	622+82.4	
<u>200</u>	TOTAL			

PLOT DATE = Thu, Sep 28 14:28:10 2006
 FILE NAME = c:\projects\20060828\20060828.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = coetallong

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY