

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	5 BR-1	La SALLE	32	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

80% FED 20% STATE

ROADWAY EX SN 050-0067
PR SN 050-2043

CONSTRUCTION TYPE CODE
I000 X080-2A

CODE NO	ITEM	UNIT	TOTAL QNTY	I000	X080-2A
51500100	NAME PLATES	EACH	1		1
54003000	CONCRETE BOX CULVERTS	CU YD	66.4		66.4
54201291	PIPE CULVERTS, TYPE 2 RCCP 36"	FOOT	88	88	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2	
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	2	2	
△ 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1087.5	1087.5	
△ 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	842	842	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
△ 70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	157	157	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	661	661	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	450	450	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	425	425	
△ 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1916	1916	
△ 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	233	233	
△ 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	32	32	
△ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	12	
△ 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16	
△ 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300105	PAVEMENT MARKING REMOVAL	FOOT	625	625	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12	12	
X0321100	GEOTEXTILE RETAINING WALL	SQ FT	578		578
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	838		838
X4402100	PAVED DITCH REMOVAL	SQ YD	236	236	
Z0022800	FENCE REMOVAL	FOOT	455	455	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
54011109	PRECAST CONCRETE BOX CULVERT 11' X 9'	FOOT	300		300

△ SPECIALTY ITEM

PLOT DATE = 7/25/2007
 FILE NAME = c:\p\proj\as\app\8884\consult\road\1\roadway\summary-of-quantities.dgn
 USER NAME = edwardd

COOMBE-BLOXDORF P.C.
 Engineers/Land Surveyors
 Springfield, Illinois
 Design Firm License No. 184-002708

REVISIONS	
NAME	DATE
BDD	4/11/07

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 IL ROUTE 71 OVER UNNAMED STREAM
 FAP RT 311, SECTION 5 BR-1
 LA SALLE COUNTY
 SCALE: DRAWN BY
 DATE: 01/13/06 CHECKED BY