

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE #	PAY ITEM	UNIT	TOTAL QUANTITY	1000-2A	X071-2A
				ROADWAY	STRUCTURE #027-0096
20200100	EARTH EXCAVATION	CU YD	263	263	
20300100	CHANNEL EXCAVATION	CU YD	491	491	
20400800	FURNISHED EXCAVATION	CU YD	221	221	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	89.8		89.8
25000210	SEEDING, CLASS 2A	ACRE	0.1	0.1	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9	9	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9	
25100630	EROSION CONTROL BLANKET	SQ YD	450	450	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	10	10	
28000300	TEMPORARY DITCH CHECKS	EACH	2	2	
28000400	PERIMETER EROSION BARRIER	FOOT	751	751	
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,162	212	950
28200200	FILTER FABRIC	SQ YD	1,162	212	950
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	84	84	
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	142	142	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	61	61	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	99	99	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	72	72	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	112	112	
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	112	112	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	36	36	
44000100	PAVEMENT REMOVAL	SQ YD	112	112	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	540	540	
44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	311	311	
44000700	APPROACH SLAB REMOVAL	SQ YD	173	173	
48203023	HOT-MIX ASPHALT SHOULDERS 8"	SQ YD	370	370	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	229.4		229.4
50300225	CONCRETE STRUCTURES	CU YD	106.5		106.5
50300255	CONCRETE SUPERSTRUCTURE	CU YD	160.9		160.9
50300260	BRIDGE DECK GROOVING	SQ YD	447		447
50300280	CONCRETE ENCASEMENT	CU YD	18.6		18.6
50300300	PROTECTIVE COAT	SQ YD	699	91	608
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	2,232		2,232
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	44,800		44,800
50800515	BAR SPLICERS	EACH	540		540
51201105	FURNISHING METAL SHELL PILES 14"	FOOT	916		916
51202305	DRIVING PILES	FOOT	916		916
51203200	TEST PILE METAL SHELLS	EACH	2		2
51205200	TEMPORARY SHEET PILING	SQ FT	1,097		1,097
51500100	NAME PLATES	EACH	1		1
52100520	ANCHOR BOLTS, 1"	EACH	48		48
54215547	METAL END SECTIONS 12"	EACH	4	4	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	56		56

* SPECIALTY ITEM

 PLOT SCALE: 1:20
 PLOT DATE: 8/9/2007
 PLOT TIME: 2:57:59 PM
 PLOT BY: A.A.
 MODEL NAME: SHEET_1

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE #	PAY ITEM	UNIT	TOTAL QUANTITY	1000-2A	X071-2A
				ROADWAY	STRUCTURE #027-0096
60100945	PIPE DRAINS 12"	FOOT	78	78	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	95		95
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B.6-24	FOOT	263	263	
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	4	4	
60900515	CONCRETE THRUST BLOCKS	EACH	4	4	
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	137.5	137.5	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	426	426	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1		1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10		10
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	83		83
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2,788		2,788
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	189		189
70400100	TEMPORARY CONCRETE BARRIER	FOOT	325		325
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	312.5		312.5
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	83.2		83.2
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,788		1,788
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	90		90
78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	278		278
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	64		64
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	34		34
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	14		14
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3		3
78200410	GUARDRAIL MARKERS - TYPE A	EACH	6		6
78200520	BARRIER WALL MARKERS - TYPE B	EACH	4		4
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	463		463
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	9		9
XX003404	TEMPORARY PAVEMENT, 8"	SQ YD	52		52
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1
X7016500	TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)	EACH	1	1	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	32		32
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2		2

* SPECIALTY ITEM



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 693 (IL-9)

SUMMARY OF QUANTITIES

SCALE: NOT TO SCALE
DATE: AUGUST 7, 2007

DRAWN BY: BMH
CHECKED BY: DWB