F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(10-92-8)(HB-1,HB-4)BR	CHAMPAIGN & VERMILION	122	7
STA.	TO STA.			
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 70001

HOT-MIX ASPHALT PAVEMENT

LOCATION	HOT-MIX ASPHALT MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SHOULDERS 6½"	HOT-MIX ASPHALT SHOULDERS	HOT-MIX ASPHALT SURFACE COURSE MIX "C", N30	HOT-MIX ASPHALT SURFACE COURSE MIX C, N50	HOT-MIX ASPHALT SURFACE COURSE MIX D, N50	HOT-MIX ASPHALT BINDER COURSE IL-19.0, N50	HOT-MIX ASPHALT BINDER COURSE IL-19.0L N30	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE MIX E, N105	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE IL-19.0, N105
STATION TO STATION	GAL.	SQ. YD.	TON	TON	TON	TON	TON	TON	TON	TON
CHAMPAIGN COUNTY										
IL49S										
306+23.50 TO 307+30.00	12.7	71.0		9.3		32.8				
307+30.00 TO 307+72.66 LT	6.3	37.9		3.2		4.4	8.4			
307+30.00 TO 41+15.00 RT	9.5	20.8		1.8		6.4	18.0			
307+72.66 TO 42+90.00 LT	47.6	17.7		1.5		20.0	46.7	206.1		
41+15.00 TO 42+90.00 RT	44.4	53.4		4.5		18.0	41.9	201.0		
42+90.00 TO 48+60.50	187.3	1141.0		95.8		117.1	274.2			
51+39.50 TO 57+10.00	187.3	1141.0		95.8		117.1	274.2			
57+10.00 TO 58+84.00 LT	44.4	51.2		4.3		17.9	41.7	222.7		
57+10.00 TO 326+00.00 RT	50.8	32.3		2.2		21.6	50.4	229.3		
58+84.00 TO 326+21.50 LT	9.5	19.2		1.6		5.9	22.5			
326+00.00 TO 326+21.50 RT	3.2	7.2		0.6		2.2	4.3			
326+21.50 TO 326+81.50	9.5	40.0		6.0		18.5				
I-74										
2294+00.00 TO 1003+85.00 WB	203.2		174.8	94.1					161.3	299.6
2294+00.00 TO 1003+85.00 EB	203.2		174.8	94.1					161.3	299.6
RAMP A										
401+00.00 TO 401+65.00	9.5		16.8	13.3		15.5				
401+65.00 TO 402+10.00	9.5			5.0		5.9	11.0			
402+10.00 TO 403+14.26	101.6					45.2	105.5	278.1		
RAMP B										
298+41.29 TO STA. 299+58.00	101.6					45.0	105.0	311.5		
299+58.00 TO 300+15.00	12.7		24.6	6.8		8.0	15.6			
300+15.00 TO 300+75.00	9.5			13.8		16.1				
RAMP C										
501+00.00 TO 501+60.00	9.5			13.0		15.2				
501+60.00 TO 502+11.00	12.7		22.0	6.1		7.2	12.4			
502+11.00 TO 503+21.57	95.2					42.7	99.6	277.7		
RAMP D										
98+50.99 TO 99+35.53	101.6					44.1	102.9	283.7		
99+35.53 TO 100+09.50	15.9		27.6	8.2		9.7	21.7			
100+09.50 TO 100+75.00	9.5			13.3		15.6				
VERMILION COUNTY										
IL 49N										
41+74.00 TO 43+83.31 LT	15.9			3.2	32.2		34.2			
41+74.00 TO 43+66.28 RT	15.9			7.4	26.6		37.9			
43+83.31 TO 44+75.00 LT	19.0			5.2	9.4		185.3			
43+66.28 TO 44+75.00 RT	22.2			6.1	11.2		173.3			
44+75.00 TO 48+60.00	114.3			43.2	79.1		68.4			
51+40.00 TO 55+00.00	107.9			43.2	73.9					
55+00.00 TO 56+00.00	41.3			11.2	20.5					
56+00.00 TO 58+24.00	28.6			5.8	69.0					
I-74									156.8	291.2
1157+10.00 TO 1163+10.00 WB	196.8		169.9	91.5					156.8	291.2
1157+10.00 TO 1163+10.00 EB	196.8		169.9	91.5						
RAMP A										
360+95.00 TO 361+98.54	28.6			4.6	55.9					
RAMP B										
258+39.71 TO 259+55.62	22.2			1.2	47.2					
RAMP C										
460+66.65 TO 461+82.52	22.2			0.8	57.5					
RAMP D										
158+49.10 TO 159+52.00	28.6			4.5	65.2					
IL 49N										
41+74.00 TO 42+26.64 LT		37.7								
41+74.12 TO 42+64.16 RT		87.8								
43+83.31 TO 48+60.00 LT		315.0								
43+66.28 TO 48+60.00 RT		327.8								
51+40.00 TO 56+35.72 LT		329.1								
51+40.00 TO 56+11.50 RT		311.5								
57+71.13 TO 58+23.92 RT		37.9								
RAMP A										
360+95.00 TO 361+16.17 LT		82.6								
360+95.00 TO 361+49.46 RT		45.0								
RAMP B										
259+25.95 TO 259+55.89		14.0								
RAMP C										
460+67.10 TO 460+89.74		9.8								
RAMP D										
159+00.54 TO 159+52.00 LT		42.3								
159+26.54 TO 159+52.00 RT		11.2								
ACTUAL TOTAL	2,368.2	4,284.4	780.4	813.7	550.7	652.1	1,755.1	2,010.1	636.2	1,181.6
USED TOTAL	2,369	4,285	780.4	814.0	551	653	1,756	2,011	637	1,183

AGGREGATE

LOCATION	AGGREGATE (PRIME COAT)	AGGREGATE SHOULDERS TYPE B, 6"
STATION TO STATION	TON	TON
CHAMPAIGN COUNTY		
IL 49 S		
306+42.61 LT (P.E.)	0.1	
306+63.25 RT (F.E.)		
42+90.00 TO 48+60.50	1.4	
51+39.50 TO 57+10.00	1.4	
VERMILION COUNTY		
IL 49 N		
44+75.00 TO 48+60.00	0.9	
51+40.00 TO 55+00.00	0.9	
CHAMPAIGN COUNTY		
IL49S		
306+23.5 TO 307+30.00 LT		25.8
306+87.00 TO 41+15.00 RT		57.1
58+84.00 TO 326+81.50 LT		65.4
326+00.00 TO 326+81.50 RT		47.9
RAMP A		
401+00.00 TO 402+10.00		48.6
RAMP B		
299+58.00 TO 300+75.00		51.7
RAMP C		
501+00.00 TO 502+11.00		49.1
RAMP D		
99+35.53 TO 100+75.00		61.7
I-74		
2294+00.00 TO 1003+85.00 WB		411.3
2294+00.00 TO 1003+85.00 EB		411.3
VERMILION COUNTY		
I-74		400.0
1157+10.00 TO 1163+10.00 WB		400.0
1157+10.00 TO 1163+10.00 EB		
ACTUAL TOTAL	4.7	2,029.9
USED TOTAL	5	2,030

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE

DATE: 06/2003

DRAWN BY: IYL

CHECKED BY: JH