

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
721	113BR1BR	DEWITT	81	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

## SUMMARY OF QUANTITIES

SHEET 1 OF 3

DEWITT COUNTY  
 RURAL  
 ROADWAY / STRUCTURE  
 IMPROVEMENTS  
 FAP 721 (IL 10)  
 STA. 238+00  
 STA. 249+00  
 80% FEDERAL  
 20% STATE  
 X081-2A  
 QUANTITY

LOCATION OF WORK:

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	247.0
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	107.0
20200100	EARTH EXCAVATION	CU YD	2,790.0
20400800	FURNISHED EXCAVATION	CU YD	2,250.0
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	266.0
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	2,733.0
* 25000300	SEEDING, CLASS 3	ACRE	2.0
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	174.0
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	174.0
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	174.0
* 25100115	MULCH, METHOD 2	ACRE	2.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	193.0
28000300	TEMPORARY DITCH CHECKS	EACH	12.0
28000400	PERIMETER EROSION BARRIER	FOOT	1,572.0
28000500	INLET AND PIPE PROTECTION	EACH	2.0
28100109	STONE RIPRAP, CLASS A5	SQ YD	1,475.0
28200200	FILTER FABRIC	SQ YD	1,475.0
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	1.0
31200100	STABILIZED SUB-BASE 4"	SQ YD	355.0
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	364.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	287.0
40600300	AGGREGATE (PRIME COAT)	TON	11.0
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	577.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	176.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	68.0
40800030	AGGREGATE (PRIME COAT)	TON	2.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	51.0
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	301.0
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	218.0
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	87.0
44000100	PAVEMENT REMOVAL	SQ YD	501.0
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	27.0

\* SPECIALTY ITEM

PLOT DATE = 8/10/2007  
 FILE NAME = c:\projects\70232\text.dgn  
 PLOT SCALE = 43.2354' / IN.  
 USER NAME = collierbw

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

F.A.P. ROUTE 721 (IL 10)  
SECTION 113BR1BR  
DEWITT COUNTY  
*Sheet 1 of 3*

SCALE: NOT TO SCALE      DRAWN BY: B.G.P.  
DATE: 07/03/07      CHECKED BY: R.M.N.