

F.A.P. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
721	(113BR)BR	DEWITT	81	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

SHEET 3 OF 3

SEEDING

STATION	STATION	SEEDING, CLASS 3 (ACRES)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH, METHOD 2 (ACRES)	TEMPORARY EROSION CONTROL SEEDING (POUND)
238+00. RT	243+13. RT	0.38	34.2	34.2	34.2	0.38	38.00
238+00. LT	243+13. LT	0.32	28.8	28.8	28.8	0.32	32.00
244+00. RT	249+00. RT	0.64	57.6	57.6	57.6	0.64	64.00
244+00. LT	249+00. LT	0.59	53.1	53.1	53.1	0.59	59.00
TOTALS		1.93	173.7	173.7	173.7	1.93	193.00
USE		2.00	174.00	174.00	174.00	2.00	193.00

END SECTIONS TO BE REMOVED

STATION	OFFSET	EACH
242+74.73	RT 40.73'	1
242+74.63	LT 44.36'	1
TOTAL		2

REMOVING INLETS

STATION	OFFSET	EACH
242+75.42	RT 18.10	1
242+75.19	LT 18.22	1
TOTAL		2

GUARDRAIL REMOVAL

STATION	OFFSET	TO	STATION	OFFSET	FOOT
240+46.01	34.48 RT		240+65.48	19.87 RT	26.14
240+65.48	19.87 RT		242+94.00	20.38 RT	228.52
241+20.66	22.16 LT		241+42.63	21.32 LT	21.99
241+42.63	21.32 LT		242+94.13	20.39 LT	151.50
246+11.84	20.58 RT		251+26.70	19.93 RT	514.86
246+11.96	20.34 LT		251+26.17	20.42 LT	514.20
251+26.17	20.42 LT		251+39.41	25.34 LT	14.46
251+26.70	19.93 RT		251+39.55	25.35 RT	14.60
TOTAL					1486.27
USE					1487.00

STEEL PLATE BEAM GUARD RAIL, TYPE A

STATION	OFFSET	TO	STATION	OFFSET	FOOT
240+45.35	41.99 RT		240+65.48	20.00 RT	33.65
240+65.48	20.00 RT		242+69.25	17.65 RT	203.85
241+69.25	20.00 LT		242+69.25	17.65 LT	100.00
245+44.75	16.50 RT		251+26.70	20.00 RT	582.08
245+44.75	16.50 LT		251+26.17	20.00 LT	581.54
251+26.17	20.00 LT		251+41.62	28.47 LT	18.46
251+26.70	20.00 RT		251+41.40	28.21 RT	17.92
TOTAL					1537.50

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)

STATION	OFFSET	TO	STATION	OFFSET	EACH
241+19.25	20.00 LT		241+69.25	20.00 LT	1.00
TOTAL					1.00

TRAFFIC BARRIER TERMINAL, TYPE 6

STATION	OFFSET	TO	STATION	OFFSET	EACH
242+69.25	17.65 RT		243+14.90	17.65 RT	1.00
242+69.25	17.65 LT		243+14.90	17.65 LT	1.00
244+99.10	16.50 RT		245+44.75	16.50 RT	1.00
244+99.10	16.50 LT		245+44.75	16.50 LT	1.00
TOTAL					4.00

GUARDRAIL MARKERS

STATION	TO	STATION	EACH
240+65.48 RT		243+14.90 RT	5
241+69.25 LT		243+14.90 LT	3
245+44.75 RT		251+26.70 RT	9
245+44.75 LT		251+26.17 LT	9
TOTAL MONODIRECTIONAL SILVER			26

BARRIER WALL MARKERS

STATION	TO	STATION	EACH
243+14.90 RT		244+99.10 RT	4
243+14.90 LT		244+99.10 LT	4
TOTAL MONODIRECTIONAL SILVER			8

TERMINAL MARKER - DIRECT APPLIED

STATION	EACH
241+19.25 LT	1
TOTAL	1

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

STATION	TO	STATION	EACH
238+00.00		242+64.88	7
246+41.13		249+00.00	4
TOTAL			11

RAISED REFLECTIVE PAVEMENT MARKER

STATION	TO	STATION	EACH
238+00.00		243+13.00	8
245+01.00		249+00.00	6
TOTAL			14

RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)

STATION	TO	STATION	EACH
243+13.00		245+01.00	4
TOTAL			4

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

STATION	OFFSET	EACH
241+10.00	55.00 LT	1
241+10.00	70.00 LT	1
249+00.00	70.00 LT	1
249+00.00	55.00 LT	1
TOTAL		4

PAINT PAVEMENT MARKING - LINE 4"

ROUTE	STATION	TO	STATION	LENGTH	4" WHITE (FOOT)	4" SKIP DASH YELLOW (FOOT)	4" NO PASSING YELLOW (FOOT)
IL 10	238+00.00		249+00.00	1,100.00	2,200.0	275.00	932.00
SUB-TOTALS					2,200.0	275.00	932.00
TOTAL WHITE					2,200.00		
TOTAL YELLOW					1,207.00		
TOTAL					3,407.00		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 F.A.P. ROUTE 721 (IL 10)
 SECTION (113BR)BR
 DEWITT COUNTY
 Sheet 3 of 3

SCALE: NOT TO SCALE
 DATE: 07/03/07
 DRAWN BY: B.B.P.
 CHECKED BY: R.M.N.