

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	LOCATION OF WORK:	
				CHAMPAIGN COUNTY RURAL ROADWAY / STRUCTURE IMPROVEMENTS FAI - 57 STA. 902+84 STA. 1258+09 90% FEDERAL 10% STATE I000-2A I000-2A QUANTITY	CHAMPAIGN COUNTY URBAN ROADWAY / STRUCTURE IMPROVEMENTS FAI - 57 STA. 544+40 TO STA. 637+33 STA. 1258+09 TO STA. 1070+77.24 90% FEDERAL 10% STATE I000-2A I000-2A QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	57,566.0	38,163.10	19,402.9
40600300	AGGREGATE (PRIME COAT)	TON	806.0	547.5	258.5
40600855	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N105	TON	924.0		924.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	8,867.0	2123.3	6743.7
40600990	TEMPORARY RAMP	SQ YD	3,718.0	1034.4	2683.6
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	23,990.0	16,596.70	7393.3
40603305	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30	TON	16,162.0	387.2	15,774.8
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	25,425.0	7479.1	17,945.9
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	60.0	40.0	20.0
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	6,058.0	1683.4	4374.6
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	94,569.0	91,186.70	3382.3
44000168	HOT-MIX ASPHALT SURFACE REMOVAL, 4 3/4"	SQ YD	11,936.0		11,936.0
44000170	HOT-MIX ASPHALT SURFACE REMOVAL, 5 1/4"	SQ YD	1,623.0		1623.0
44000173	HOT-MIX ASPHALT SURFACE REMOVAL, 6"	SQ YD	9,303.0		9303.0
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	117,430.0	91,186.76	26,243.24
44200523	CLASS A PATCHES, TYPE IV, 7 INCH	SQ YD	2,886.0	2886.0	
44200547	CLASS A PATCHES, TYPE IV, 9 INCH	SQ YD	960.0		960.0
44200561	CLASS A PATCHES, TYPE I, 11 INCH	SQ YD	379.0	361.0	18.0
44200565	CLASS A PATCHES, TYPE II, 11 INCH	SQ YD	621.0	577.0	44.0
44200569	CLASS A PATCHES, TYPE III, 11 INCH	SQ YD	36.0	36.0	
44200571	CLASS A PATCHES, TYPE IV, 11 INCH	SQ YD	40.0	40.0	
44200573	CLASS A PATCHES, TYPE I, 12 INCH	SQ YD	8.0		8.0
44200577	CLASS A PATCHES, TYPE II, 12 INCH	SQ YD	14.0		14.0