

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	2(B-5, B-6)	PIKE	112	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
			I000 80% FEDERAL 20% STATE BREWSTER	I000 80% FEDERAL 20% STATE BROWN	X028-2A 80% FEDERAL 20% STATE BREWSTER	X081-2A 80% FEDERAL 20% STATE BROWN
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	240	240		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	48	48		
44000198*	HOT MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	64			
44000100	PAVEMENT REMOVAL	SQ YD	823	412	411	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	149	149		
44000920	<i>BITUMINOUS</i> CONCRETE SHOULDER REMOVAL	SQ YD	328	163	165	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	159	81	78	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	366	117	249	
50100200*	REMOVAL OF EXISTING STRUCTURES	L SUM	1			1
50100300*	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1
50105220	PIPE CULVERT REMOVAL	FOOT	97	57	40	
50200100	STRUCTURE EXCAVATION	CU YD	1328			1014
50300100	FLOOR DRAINS	EACH	6			6
50300225	CONCRETE STRUCTURES	CU YD	134			94
*	SEE SPECIAL PROVISIONS					

PLOT DATE : 7/21/2007
 FILE NAME : c:\p\projects\652484\ybaa\final\sum_of_quantities.dgn
 PLOT SCALE : 1/8"=1'-0"
 USER NAME : laughtin

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SHEET 4 OF 9
FAP 304 (IL 96)
SECTION 2(B-5, B-6)
PIKE COUNTY

Rev.

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE