

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	2B-5	PIKE	112	78
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

Driveway Schedule

LOCATION	TYPE OF ENTRANCE	EX MATERIAL TYPE	WIDTH	RT OFFSET	LT OFFSET	LENGTH (FROM EDGE OF PVT/BIT SHLD TO LIMITS OF IMPROVEMENT)	PR BIT, CONC. THICKNESS	DRIVEWAY PAVEMENT REMOVAL	PREP OF BASE	AGG. BASE REPAIR	AGGREGATE BASE COURSE TY-B	INCIDENTAL BIT. SUR. SUPERPAVE	P. C. C. DRIVEWAY PAVEMENT 6"	P. C. C. DRIVEWAY PAVEMENT 8"
(LT / RT) (STA) ( + )	(FE / PE/ CE/ MB) (RURAL) / (URBAN)	(EARTH / AGG. / BIT. / P. C. C.)	FT.	FT.	FT.	FT.	IN.	SO YD	SO YD	TON	TON	TON	SO. YD.	SO. YD.
BREWSTER CREEK														
FAP 304														
STA 400+33.75	FE - URBAN SIZE	AGG	31			13	3.5	20	56.2	0.6	19.2	7.6		
STA 402+00.00	PE, MB - RURAL	BIT			28.4			68.9						
STA 403+06.33	FE - RURAL	AGG	24			81.5	3.5		171.6	0.4	58.6	5.8		
STA 406+75.36	PE, MB - RURAL	BIT			39.5			59.3						
CH 13														
STA 10+31.43	PE - RURAL	BIT	12			20.76	3.5		31.0	0.5	10.6	6.1		
STA 11+55.57	PE - RURAL	BIT	16			32	3.5		81.6	1.2	27.9	16.0		
SUBTOTAL								148.2	340.4	2.7	116.3	35.5		
USE								149	341	3	117	36		
BROWN CREEK														
FAP 304														
STA 454+92.11	FE - RURAL	AGG	24			144.63	3.5		332.6	0.4	113.6	5.9		
SUBTOTAL									332.6	0.4	113.6	5.9		
USE									333	1	114	6		
TOTAL								149	674	4	231	42		

ct:\Projects\d652404\psba\_f.inel\ent\ent\_3r-psba.dgn  
7/31/2007  
\*REF01

REVISIONS	
NAME	DATE
JCN	2/19/03

**SHEET 3 OF 3**

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**DISTRICT SIX**  
**SCHEDULES FOR RURAL / URBAN**  
**ENTRANCE & MAILBOX TURNOUT**  
**W / O CONCRETE GUTTER**  
**(3R - PROJECTS)**

SCALE: VERT.      DRAWN BY CADD  
                  HORIZ.      CHECKED BY JCN  
DATE: FEBRUARY 23, 1999