

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685	113B-2	HANCOCK	45	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	CONSTRUCTION CODE
				ROADWAY FAP 685 80% FED 20% STATE 1000-2A	STRUCTURE SN 034-2519 80% FED 20% STATE X028-2A
20100500	TREE REMOVAL, ACRES	ACRE	1.5	1.5	
20200100	EARTH EXCAVATION	CU YD	2175	2175	
20800150	TRENCH BACKFILL	CU YD	43	43	
25000200	SEEDING, CLASS 2	ACRE	1.25	1.25	
25000400	NITROGEN FERTILIZER NUTRIENT	<i>POUND</i>	113	113	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	<i>POUND</i>	113	113	
25000600	POTASSIUM FERTILIZER NUTRIENT	<i>POUND</i>	113	113	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	2.5	2.5	
25100115	MULCH, METHOD 2	ACRE	1.25	1.25	
25101005	HEAVY DUTY EXCELSIOR BLANKET	SO YD	402	402	
28000250	TEMPORARY EROSION CONTROL SEEDING	<i>POUND</i>	125	125	
28000400	PERIMETER EROSION BARRIER	FOOT	1600	1600	
28000500	INLET AND PIPE PROTECTION	EACH	4	4	
28001000	AGGREGATE (EROSION CONTROL)	TON	150	150	
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	<i>946</i>	<i>946</i>	
28200200	FILTER FABRIC	SO YD	1420	1420	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	89	89	
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SO YD	1140	1140	
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SO YD	100	100	
35800100	PREPARATION OF BASE	SO YD	484	484	
35800200	AGGREGATE BASE REPAIR	TON	122	122	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2.6	2.6	
40600300	AGGREGATE (PRIME COAT)	TON	1	1	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	67	67	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL 9/96 OVER OPPOSUM CREEK
FAP 685 SECTION 113B-2
HANCOCK COUNTY

SCALE _____ DRAWN BY GEW
DATE #DATE _____ CHECKED BY MJS

TJD PROJ. #103307-11
PLOT DATE : 4-9-27-2007 11:42:43AM
FILE NAME : #FILE#

The Upchurch Group
HILLSIDE, IL (708) 440-2451
MATTSON, IL (217) 236-9177

Rev.