

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685	113B-2	HANCOCK	45	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY FAP 685 80% FED 20% STATE 1000-2A	STRUCTURE SN 034-2519 80% FED 20% STATE X028-2A
40600982	HOT-MIX ASPHALT SURFACE REMOVAL -- BUTT JOINT	SO YD	148	148	
40600990	TEMPORARY RAMP	SO YD	26	26	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	150	150	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	93	93	
44000100	PAVEMENT REMOVAL	SO YD	203	203	
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SO YD	42	42	
48101300	AGGREGATE SHOULDERS, TYPE B (SPECIAL)	TON	79	79	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	122	122	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105210	REMOVE EXISTING CULVERTS	FOOT	36	36	
50105220	PIPE CULVERT REMOVAL	FOOT	46	46	
50800105	REINFORCEMENT BARS	POUND	94810		94810
50800515	BAR SPLICERS	EACH	160		160
51500100	NAME PLATES	EACH	1		1
54003000	CONCRETE BOX CULVERTS	CU YD	301.2		301.2
54200451	PIPE CULVERTS, TYPE I RCCP 36"	FOOT	151	151	
54201480	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	100	100	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	3	3	
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	500	500	
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	125	125	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	466	466	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	7	7	
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	1	1	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**  
**IL 9/96 OVER OPPOSUM CREEK**  
**FAP 685 SECTION 113B-2**  
**HANCOCK COUNTY**

SCALE \_\_\_\_\_ DATE \_\_\_\_\_

DRAWN BY CEW  
 CHECKED BY MJS

\*SPECIALTY ITEMS

TUG PROJ: 61031007-11  
 PLOT DATE: 4/27/2007 11:47:43AM  
 FILE NAME: #FILE#

**The Upchurch Group**  
 HILLSDALE, IL 60931-440-2231  
 MATTOON, IL (217) 245-5177