

S.B.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
15B	(17C)B	WAYNE	17	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

GENERAL NOTES

PERIMETER EROSION BARRIER IS FOR PLACEMENT AT THE TOE OF THE PROPOSED FILL SLOPE ALONG THE TOTAL LENGTH OF THE PROJECT. EROSION CONTROL BLANKET IS FOR PLACEMENT ON ALL NEW SLOPE CONSTRUCTION.

THE TOTAL QUANTITY OF PAINT PAVEMENT MARKING-LINE 4 INCH CONSISTS OF 104 FEET OF WHITE AND 20 FEET OF YELLOW.

THE PROCESS OF REMOVAL OF UNSUITABLE MATERIAL AND REPLACING WITH ROCK FILL SHALL BE A CONTINUOUS OPERATION AND CLOSELY MONITORED BY THE CONTRACTOR. ANY UNSUITABLE MATERIAL REMOVED DURING THE COURSE OF A DAY SHALL BE REPLACED WITH ROCK FILL THAT SAME DAY. THE SLOPE STABILITY OF THE NEW CULVERT CUT DEPENDS ON THIS MATERIAL BEING IN PLACE.

AGGREGATE FOR AGGREGATE SHOULDERS, TYPE B SHALL BE CRUSHED STONE, CRUSHED CONCRETE OR RAP.

THE REMOVAL OF ALL EARTHWORK, SUB-GRADE AND PAVEMENT WITHIN THE LIMITS OF THE EXISTING BRIDGE STRUCTURE SHALL BE INCLUDED IN THE COST OF THE PAY ITEM REMOVAL OF EXISTING STRUCTURES. ALL EARTHWORK AND SUB-GRADE REMOVAL NECESSARY TO FACILITATE THE REMOVAL OF THE EXISTING BRIDGE STRUCTURE WHILE MAINTAINING SLOPE STABILITY (1:1 MINIMUM) SHALL BE INCLUDED IN THE COST OF THE PAY ITEM REMOVAL OF EXISTING STRUCTURES. ALL PAVEMENT REMOVAL IN THESE AREAS WILL BE PAID FOR AS PAVEMENT REMOVAL.

THE LOCATIONS AND/OR DEPTHS OF UNDERGROUND UTILITIES SHOWN HAVE BEEN TAKEN FROM INFORMATION FURNISHED BY THE UTILITY OWNERS AND MUST BE CONSIDERED APPROXIMATE. FIELD MARKINGS OF ACILITIES IN CRITICAL AREAS MAY BE OBTAINED BY PROVIDING A MINIMUM OF 96 HOURS ADVANCE NOTICE THROUGH THE J.U.L.I.E. SYSTEM BY CALLING 800-892-0123.

INDEX OF SHEETS

SHEET NO	TITLE
1	COVER SHEET
2	GENERAL NOTES, INDEX OF SHEETS, LIST OF HIGHWAY STANDARDS
3	SUMMARY OF QUANTITIES
4	TYPICAL SECTIONS
5	PLAN SHEET
6	TRAFFIC CONTROL PLAN
7-12A	BOX CULVERT DETAILS
13-17	CROSS SECTIONS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED FOLLOWING THE LAST NUMBERED SHEET OF THE PLANS.

STD. NO.	DESCRIPTION
000001-04	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-01	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
420001-06	PAVEMENT JOINTS
420101-03	24' JOINTED PCC PAVEMENT
515001-02	NAME PLATE FOR BRIDGES
630001-07	STEEL PLATE BEAM GUARDRAIL
630101-07	GUARDRAIL MOUNTED ON EXISTING CULVERTS
630301-04	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
635006-02	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-01	REFLECTOR MARKER AND MOUNTING DETAILS
701001-01	OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY
701006-02	OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
701011-01	OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701301-02	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701311-02	LANE CLOSURE 2L, 2W MOVING OPERATIONS-DAY ONLY
702001-06	TRAFFIC CONTROL DEVICES
780001-01	TYPICAL PAVEMENT MARKINGS
781001-02	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS

PLOT DATE = 8/24/2007
 FILE NAME = c:\p\projects\74092\shutover-74092.dgn
 USER = s3011000 / IN

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**GENERAL NOTES
AND
INDEX OF SHEETS**

SCALE: VERT. _____
 DATE: _____

DRAWN BY _____
 CHECKED BY _____