

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1669		COLES	17	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		SN 015-0069	SN 015-0070
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	247	83	164
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	60	37	23
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	431	260	171
48101200	AGGREGATE SHOULDERS, TYPE B	TON	14	6	8
50102400	CONCRETE REMOVAL	CU YD	3.1	3.1	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3.6	3.6	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	250	250	
50800515	BAR SPLICERS	EACH	6	6	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	33	33	
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	431	260	171
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	484	304	180
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	2	1	1
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	2	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5	0.5
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	3	3	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	97	46	51
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3453	2097	1356
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	481	234	247
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2249	1507	742
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3	2	1
* 78100300	REPLACEMENT REFLECTOR	EACH	9	4	5
78300100	PAVEMENT MARKING REMOVAL	SQ FT	700	499	201
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	9	4	5
Z0003700	BEARING PAD ADJUSTMENT	EACH	42	22	20
Z0032700	KEYWAY REPAIR	FOOT	484	304	180

PLOT DATE = 8/27/2007
 FILE NAME = c:\projects\74267\shltacq-74267.dgn
 PLOT SCALE = 20.0000 / IN.
 USER NAME = sterfennik

* SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE
 HORIZ.

DRAWN BY
 CHECKED BY