

FILE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	95-(5,6)RS-1	WASHINGTON	83	11
STA. _____ TO STA. _____		CONTRACT NO.: 76A39		

SURFACE REMOVAL SCHEDULE

LOCATION			HMA SURFACE REMOVAL 2"	HMA SURFACE REMOVAL 2 1/4"	HMA SURFACE REMOVAL 3"	HMA SURFACE REMOVAL 3/4"	HMA SURFACE REMOVAL - VARIABLE DEPTH
STA	TO	STA	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
FAI 64 EAST BOUND							
2935+25.00	TO	2943+00.00	2152.78				
2943+00.00	TO	2973+00.00	8333.33				
2973+00.00	TO	2981+45.00	2347.22				
2981+45.00	TO	2983+45.00		355.56			
2983+45.00	TO	3002+00.00	5152.78				
3002+00.00	TO	3033+00.00	8611.11				
3033+00.00	TO	3063+00.00	8333.33				
3063+00.00	TO	3093+00.00	8333.33				
3093+00.00	TO	3123+00.00	8333.33				
3123+00.00	TO	3153+00.00	8333.33				
3153+00.00	TO	3183+00.00	8333.33				
3183+00.00	TO	3213+00.00	8333.33				
3213+00.00	TO	3221+35.00	2319.44				
3221+35.00	TO	3223+35.00		355.56			
3223+55.00	TO	3243+00.00	5402.78				
3243+00.00	TO	3262+84.00	5511.11				
3264+46.00	TO	3273+00.00	2372.22				
3273+00.00	TO	3282+12.00	2533.33				
3284+18.00	TO	3288+00.00	1061.11				
3288+00.00	TO	3303+00.00	4166.67				
3303+00.00	TO	3333+00.00	8333.33				
3333+00.00	TO	3355+51.00	6252.78				
FAI 64 WEST BOUND							
2935+25.00	TO	2943+00.00	2152.78				
2943+00.00	TO	2973+00.00	8333.33				
2973+00.00	TO	2981+45.00	2347.22				
2981+45.00	TO	2983+45.00		355.56			
2983+45.00	TO	3002+00.00	5152.78				
3002+00.00	TO	3033+00.00	8611.11				
3033+00.00	TO	3063+00.00	8333.33				
3063+00.00	TO	3093+00.00	8333.33				
3093+00.00	TO	3123+00.00	8333.33				
3123+00.00	TO	3153+00.00	8333.33				
3153+00.00	TO	3183+00.00	8333.33				
3183+00.00	TO	3213+00.00	8333.33				
3213+00.00	TO	3221+17.00	2269.44				
3221+17.00	TO	3223+67.00		355.56	834.00		
3223+67.00	TO	3243+00.00	5369.44				
3243+00.00	TO	3262+98.00	5550.00				
3264+59.00	TO	3273+00.00	2336.11				
3273+00.00	TO	3282+91.00	2752.78				
3284+97.00	TO	3288+00.00	841.67				
3288+00.00	TO	3303+00.00	4166.67				
3303+00.00	TO	3333+00.00	8333.33				
3333+00.00	TO	3355+51.00	6252.78				
RAMPS							
100+88.00	TO	109+15.00					
109+15.00	TO	120+79.00			1435.00		
200+00.00	TO	206+95.00			1011.00		27
206+95.00	TO	213+02.00					27
300+30.00	TO	305+75.00			800.00		27
305+75.00	TO	316+25.00					
400+60.00	TO	407+93.00					27
407+93.00	TO	419+76.00			1553.00		
TOTAL			229020	1423	834	4799	108

EASTBOUND RESURFACING SCHEDULE

LOCATION			BIT. MAT'L PRIME COAT	AGGREGATE PRIME COAT	HMA SHOULDER 2 1/4"	SHOULDER RUMBLE STRIP	AGGREGATE WEDGE SHLDR TYPE B	HMA BINDER COURSE 2 1/4"	LEVELING BINDER 1"	HMA SURFACE COURSE 2"	INCIDENTAL HMA ASPHALT SURFACING	STRIP REFLECTIVE CRACK CONTROL
STA	TO	STA	(TON)	(TON)	(TON)	(FOOT)	(TON)	(TON)	(TON)	(TON)	(TON)	(FOOT)
FAI 64 EAST BOUND												
2934+95.00	TO	2943+00.00	1.85	6.84	288.27	1610.00	128.76	295.84		262.96		
2943+00.00	TO	2973+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
2973+00.00	TO	2981+45.00	1.93	7.19	302.60	1690.00	135.16	310.54		276.03		
2981+45.00	TO	2983+45.00	0.11	0.86	71.62	400.00	31.99					
2983+45.00	TO	3002+00.00	4.28	15.89	679.08	3710.00	296.71	681.71		605.97		
3002+00.00	TO	3033+00.00	7.12	26.44	1119.71	6200.00	495.86	1139.25		1012.66	45	
3033+00.00	TO	3063+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
3063+00.00	TO	3093+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
3093+00.00	TO	3123+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
3123+00.00	TO	3153+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
3153+00.00	TO	3183+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
3183+00.00	TO	3213+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
3213+00.00	TO	3221+35.00	1.92	7.09	299.01	1670.00	133.56	306.86		272.77		
3221+35.00	TO	3223+35.00	0.11	0.86	71.62	400.00	31.99					
3223+55.00	TO	3243+00.00	4.49	16.66	712.77	3890.00	311.11	714.79		635.37		
3243+00.00	TO	3262+84.00	4.56	16.94	718.60	3968.00	317.35	729.12		648.10	45	
3264+46.00	TO	3273+00.00	1.96	7.25	305.82	1708.00	136.60	313.85		278.97		335
3273+00.00	TO	3282+12.00	2.09	7.75	326.59	1824.00	145.88	335.16		297.92		
3284+18.00	TO	3288+00.00	0.87	3.25	136.79	764.00	61.10	140.39		124.78		
3288+00.00	TO	3303+00.00	3.43	12.75	537.15	3000.00	239.93	551.25		490.00		1003
3303+00.00	TO	3333+00.00	6.89	25.50	1074.30	6000.00	479.86	1102.50		980.00		
3333+00.00	TO	3355+51.00	5.17	19.13	806.09	4502.00	360.06	827.24		735.33	45	
RAMPS												
300+30.00	TO	305+75.00	0.53	0.30	21.25	230.00	70.64		47.04	94.08		
305+75.00	TO	315+60.00	1.44	3.28	232.71	1970.00	127.68		103.02	206.03		
401+65.00	TO	407+93.00	0.92	2.10	148.76	1400.00	81.40		65.68	131.36		
407+93.00	TO	419+76.00	1.05	0.64	45.69	220.00	153.34		91.32	182.64		
SUB TOTAL =			98.9	360	15419	87156	7098	15166	307	14095	135	1338

PLOT DATE = 9/5/2007
FILE NAME = c:\puro\puro\95\1207\plan\shl\81207b.dgn
SCALE = 1/8" = 1'-0"
REFERENCE = # 1000

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
RESURFACING SCHEDULES
FAI ROUTE 64
SECTION 95-(5,6)RS-1
WASHINGTON COUNTY
SCALE: VERT. _____
HORIZ. _____
DATE _____ DRAWN BY _____
CHECKED BY _____