FAI ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
64	95-(5,6)RS-1	WASHINGTON	83	15
STA. _____		TO STA. _____		
CONTRACT NO.: 76A39				

GUARDRAIL SCHEDULE

REMOVAL LOCATION		INSTALLATION LOCATION		SIDE	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL	TRAFFIC BARRIER TERMINAL TYPE 1 (SPL) TANGENT	TRAFFIC BARRIER TERMINAL TYPE 1 (SPL) FLARED	TRAFFIC BARRIER TERMINAL TYPE 2	TRAFFIC BARRIER TERMINAL TYPE 5	TRAFFIC BARRIER TERMINAL TYPE 6	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL MARKERS
					FT	FT	EACH	EACH	EACH	EACH	EACH	EACH	EACH
I-64 EB MAINLINE		I-64 EB MAINLINE											
STATION	STATION	STATION	STATION										
2982+28	2983+28	2982+03	2983+28	L	100.0	75.0		1	1			1	2
3224+80	3225+80	3224+55	3225+80	L	100.0	75.0		1	1			1	2
3258+72	3262+84	3258+15	3262+84	R	412.5	375.0	1				1	1	6
3261+22	3262+84	3258+53	3262+84	L	162.5	337.5	1				1	1	5
3264+44	3268+19	3264+44	3268+44	R	375.0	375.0			1	1			6
3279+33	3282+20	3278+51	3282+20	R	287.5	275.0	1				1	1	4
3279+95	3282+20	3277+89	3282+20	L	225.0	337.5	1				1	1	5
I-64 WB MAINLINE		I-64 WB MAINLINE											
STATION	STATION	STATION	STATION										
2982+81	2983+81	2982+81	2984+06	L	100.0	75.0		1	1			1	2
3225+33	3226+46	3225+33	3226+58	L	112.5	75.0		1	1			1	2
3256+72	3262+84	3256+47	3262+84	R	612.5	612.5			1	1			9
3264+44	3266+32	3264+44	3268+76	L	187.5	337.5	1				1	1	5
3264+44	3270+32	3264+44	3270+88	R	587.5	550.0	1				1	1	8
3284+30	3286+55	3284+30	3288+62	L	225.0	337.5	1				1	1	5
3284+30	3287+05	3284+30	3287+99	R	275.0	275.0	1				1	1	4
TOTAL					3762.5	4112.5	8	4	6	2	8	12	65

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GUARDRAIL SCHEDULES

FAI ROUTE 64
SECTION 95-(5,6)RS-1
WASHINGTON COUNTY

DRAWN BY:

PLOT DATE: 8/21/2007

$$DATE$$
8/21/2007
c:\projects\ws01207\plan\pln01207b.dgn
$$REF$$
$$REF$$