

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 332	*	WHITE	13	3
FED. ROAD DIST. NO. 7	SECTION	FED. AID PROJECT		

\* D9 CM BRIDGE REPAIR FY 08-1  
CONTRACT NO. 78015

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: SAFETY-2A		100% STATE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
42001300	PROTECTIVE COAT	SQ YD	114.2
50102400	CONCRETE REMOVAL	CU. YD	22.1
50104000	BRIDGE RAIL REMOVAL	FOOT	156.0
50300100	FLOOR DRAINS	EACH	8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	33.2
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1530
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	16
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5630
X0325701	STEEL RAILING, TYPE 2399	FOOT	156.0
52000110	PREFORMED JOINT STRIP SEAL	FOOT	76
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	16
52100520	ANCHOR BOLTS, 1"	EACH	32
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	357

CONSTRUCTION TYPE CODE: SAFETY-2A		100% STATE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
70400100	TEMPORARY CONCRETE BARRIER	FOOT	270
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	270
* 78001110	PAINT PAVEMENT MARKING LINE - 4"	FOOT	688
X6333500	TRAFFIC BARRIER TERMINAL REMOVAL	EACH	4
X0321781	MECHANICAL SPLICE	EACH	285
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
50800515	BAR SPLICERS	EACH	22
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2

\* SPECIALTY ITEMS

PAINT PAVEMENT MARKING - LINE 4"

COLOR	QUANTITY (FOOT)
WHITE	540
YELLOW	148
TOTAL	688