F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	*	WILL	64	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* 02-11106-01-BR CONTRACT NO. 83949

SUMMARY OF QUANTITIES

	PAY ITEM NO.	IDOT CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY (1000-2A)	BRIDGE X021-2A
	38	50105220	PIPE CULVERT REMOVAL	FOOT	62	62	
	39	50200100	STRUCTURE EXCAVATION	CU YD	2,355		2,355
	40	50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	270		270
	41	50300225	CONCRETE STRUCTURES	CU YD	942		942
	42	50300255	CONCRETE SUPERSTRUCTURE	CU YD	108		108
	43	50300260	BRIDGE DECK GROOVING	SQ YD	262		262
	44	50300300	PROTECTIVE COAT	SQ YD	325		325
	45	50300510	RUSTICATION FINISH	SQ FT	4975		4975
	46	50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1,623		1,623
	47	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	142884		142884
	48	50800515	BAR SPLICERS	EACH	88		88
	49	51500100	NAME PLATES	EACH	1		1
	50	52000110	PREFORMED JOINT STRIP SEAL	FOOT	88		88
	51	52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	6		6
	52	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2	
	53	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2	
	54	54213867	STEEL END SECTIONS 12"	EACH	4	4	
	55	5421A012	PIPE CULVERTS, CLASS A, TYPE 1 12" (TEMPORARY)	FOOT	24	24	
	56	55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	20	20	
	57	55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	43	43	
	58	58700200	BRIDGE SEAT SEALER	SQ FT	204		204
	59	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	564		564
	60	60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4	4	
	61	60100945	PIPE DRAINS 12"	FOOT	50	50	
	62	60107600	PIPE UNDERDRAINS 4"	FOOT	879	879	
	63	60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	60	60	
	64	60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	527		527
	65	60200905	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 9 FRAME AND GRATE	EACH	2	2	
	66	60900315	TYPE D INLET BOX, STANDARD 609006	EACH	2	2	
	67	60900515	CONCRETE THRUST BLOCKS	EACH	2	2	
*	68	63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	340	340	
*	69	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
*	70	63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	6	6	
*	71	63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	45	45	
*	72	63500105	DELINEATORS	EACH	6	6	
	73	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	
	74	67100100	MOBILIZATION	L SUM	1	1	

* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

LOCKPORT TOWNSHIP HIGHWAY DEPARTMENT
TR216A HIGH ROAD OVER LONG RUN CREEK
SECTION 02-11106-01-BR

SUMMARY OF QUANTITIES II

SCALE: N/A DRAWN BY: JB
DATE: 9-07-2007 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616 0600

..\SCOOURHLD.DGN ..\TTBOORE8.DGN ..\SCOOURHLD.DGN
9-07-2007, 8:06:35 S:\DOCUMENT\02239402\CIVIL\DGN\SCOOURHLD.DGN
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63
BONDHLJO