

REF#	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
2744	06-00241-00-PV	COOK	115	3
STA.		TO STA.		
ALMOB		SURFACE TRANSPORTATION FUNDING		

CONTRACT NUMBER 83968

ITEM NO.	PAY ITEM NO.	PAY ITEM DESCRIPTION	UNIT	1000-2A QUANTITY	NON-PART. QUANTITY	TOTAL QUANTITY
1	20101000	TEMPORARY FENCE	FOOT	2,000		2,000
2	20101200	TREE ROOT PRUNING	EACH	382		382
3	20101400	NITROGEN FERTILIZER NUTRIENT	LB	94		94
4	20101500	PHOSPHORUS FERTILIZER NUTRIENT	LB	94		94
5	20101600	POTASSIUM FERTILIZER NUTRIENT	LB	94		94
6	20101700	SUPPLEMENTAL WATERING	UNIT	8		8
7	20200100	EARTH EXCAVATION	CU YD	2,100		2,100
8	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	267		267
9	20400800	FURNISHED EXCAVATION	CU YD	250		250
10	20800250	TRENCH BACKFILL, SPECIAL	CU YD	8,184		8,184
11	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	2,928		2,928
12	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	12,100		12,100
13	21300010	EXPLORATION TRENCH, SPECIAL	FOOT	100		100
14	25000400	NITROGEN FERTILIZER NUTRIENT	LB	428		428
15	25000500	PHOSPHORUS FERTILIZER NUTRIENT	LB	428		428
16	25000600	POTASSIUM FERTILIZER NUTRIENT	LB	428		428
17	25200110	SODDING, SALT TOLERANT	SQ YD	12,100		12,100
18	28000400	PERIMETER EROSION BARRIER	FOOT	9,000		9,000
19	28000510	INLET FILTERS	EACH	98		98
20	31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	23		23
21	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	770		770
22	35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	770		770
23	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	10,100		10,100
24	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	20		20
25	40600535	LEVELING BINDER (HAND METHOD), N70	TON	20		20
26	40600895	CONSTRUCTING TEST STRIP	EACH	2		2
27	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	763		763
28	40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	957		957
29	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	9,816		9,816
30	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4,908		4,908
31	42001300	PROTECTIVE COAT	SQ YD	7,769		7,769
32	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1,675		1,675
33	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	40,000		40,000
34	42400800	DETECTABLE WARNINGS	SQ FT	3,420		3,420
35	44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	50,082		50,082
36	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,402		1,402
37	44000600	SIDEWALK REMOVAL	SQ FT	40,000		40,000
38	44201074	CLASS B PATCHES, TYPE I	SQ YD	439		439
39	44201076	CLASS B PATCHES, TYPE II	SQ YD	2,634		2,634
40	44201078	CLASS B PATCHES, TYPE III	SQ YD	878		878
41	44201080	CLASS B PATCHES, TYPE IV	SQ YD	439		439
42	44400100	FIBER GLASS FABRIC REPAIR SYSTEM	SQ YD	50,082		50,082
43	550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	2,974		2,974
44	550A2530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 15"	FOOT	384		384
45	550A2560	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 24"	FOOT	30		30
46	550A2720	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 3 12"	FOOT	392		392
47	550A2730	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 3 15"	FOOT	1,633		1,633
48	550A2740	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 3 18"	FOOT	787		787
49	550A2760	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 3 24"	FOOT	384		384
50	56103000	DUCTILE IRON WATER MAIN 6"	FOOT		120	120
51	56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	20		20
52	60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	31		31
53	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	10		10
54	60220400	MANHOLES, TYPE A, SPECIAL, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	35		35
55	60223100	MANHOLES, TYPE A, SPECIAL, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4		4
56	60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	10		10
57	60248700	VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2		2
58	60250200	CATCH BASINS TO BE ADJUSTED	EACH	102		102
59	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	10		10
60	60255500	MANHOLES TO BE ADJUSTED	EACH	2		2
61	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	13		13
62	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	11		11
63	60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	1		1
64	60266500	VALVE VAULTS TO BE REMOVED	EACH		1	1
65	60266600	VALVE BOXES TO BE ADJUSTED	EACH		1	1

ITEM NO.	PAY ITEM NO.	PAY ITEM DESCRIPTION	UNIT	1000-2A QUANTITY	NON-PART. QUANTITY	TOTAL QUANTITY
66	60266910	VALVE BOXES TO BE REMOVED	EACH		1	1
67	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	150		150
68	60404800	FRAMES AND GRATES, TYPE 11	EACH	87		87
69	60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	15		15
70	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	143		143
71	60500040	REMOVING MANHOLES	EACH	12		12
72	60500050	REMOVING CATCH BASINS	EACH	31		31
73	60500060	REMOVING INLETS	EACH	10		10
74	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL M	8		8
75	67100100	MOBILIZATION	L SUM	1		1
76	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1		1
77	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1		1
78	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6,600		6,600
79	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	53		53
80	70300725	TEMPORARY PAINT PAVEMENT MARKING 4" WHITE	FOOT	18,276		18,276
81	70300735	TEMPORARY PAINT PAVEMENT MARKING 6" WHITE	FOOT	4,465		4,465
82	70300760	TEMPORARY PAINT PAVEMENT MARKING 24" WHITE	FOOT	1,078		1,078
83	70300825	TEMPORARY PAINT PAVEMENT MARKING 4" YELLOW	FOOT	18,276		18,276
84	72000100	SIGN PANEL - TYPE 1	SQ FT	500		500
85	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	25		25
86	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	1,500		1,500
87	73100110	BASE FOR TELESCOPING SIGN SUPPORT, SPECIAL	EACH	50		50
88	78000100	THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	432		432
89	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5,890		5,890
90	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4,465		4,465
91	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	112		112
92	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,161		2,161
93	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,078		1,078
94	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	256		256
95	78300100	PAVEMENT MARKING REMOVAL	SQ FT	14,155		14,155
96	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	11		11
97	88600100	DETECTOR LOOP, TYPE I	FOOT	4,000		4,000
98	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	1200		1200
99	X0323221	PLUG AND ABANDON EXISTING PIPE	CU YD	17		17
100	X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	98		98
101	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	85		85
102	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,805		2,805
103	X7015012	CHANGEABLE MESSAGE SIGN, SPECIAL	EACH	2		2
104	XX003455	POROUS GRANULAR EMBANKMENT, SUBGRADE	TON	500		500
105	XX003560	CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	22,225		22,225
106	XX003668	PRECONSTRUCTION VIDEO TAPING	L SUM	1		1
107	XX004689	SANITARY SERVICE TO BE ADJUSTED	EACH	35		35
108	XX004762	WATER SERVICE LINE TO BE ADJUSTED	EACH	35		35
109	XX004812	VIDEO TAPING OF SEWERS	FOOT	13,890		13,890
110	XX004878	MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	L SUM	1		1
111	XX005063	CLASS B PATCHES	SQ YD	4,956		4,956
112	XX005065	CLASS B PATCHES (HIGH EARLY CONCRETE)	SQ YD	740		740
113	XX005751	MANHOLE REHABILITATION	FOOT	579		579
114	XX005617	CONNECTING TO EXISTING MANHOLES BY CORE DRILLING	EACH	55		55
115	XX005655	STORM SEWER REMOVAL UNDER 18"	FOOT	283		283
116	XX005688	STORM SEWER, DUCTILE IRON PIPE, CLASS 52 8"	FOOT	1,135		1,135
117	XX005689	STORM SEWER, DUCTILE IRON PIPE, CLASS 52 10"	FOOT	273		273
118	XX005758	TEMPORARY PAVEMENT	TON	30		30
119	XX005879	DRAINAGE RESTRICTOR ASSEMBLY	EACH	65		65
120	XX006464	DOMESTIC WATER SERVICE BOX TO BE ADJUSTED (SPECIAL)	EACH	50		50
121	XX006698	TREE PROTECTION AND PRESERVATION	EACH	382		382
122	LR430030	CONCRETE PAVER PAVEMENT	SQ YD	10		10
123	Z0019600	DUST CONTROL WATERING	UNIT	10		10
124	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1
125	Z0067700	STEEL CASINGS 20"	FOOT		66	66
126	Z0076600	TRAINERS	HOUR	3,000		3,000
127	XX007147	REMOVE AND REPLACE LAWN SPRINKLER SYSTEM	FOOT	50		50
128	XX007746	STORM SEWERS, TYPE 2 WYE 12" PIPE - 12" BRANCH	EACH	3		3

^ DENOTES SPECIALTY ITEM
^^ DENOTES CONSTRUCTION TYPE CODE Y080

REVISIONS	
NAME	DATE
PREFINAL REVIEW	05.18.07

CITY OF EVANSTON
SUMMARY OF QUANTITIES
RIDGE AVENUE IMPROVEMENT

DATE: 8/31/2007
DESIGNED BY: STC
TECHNICIAN: JRR
CHECKED BY: RTM