

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
827	12Z-3, 12BR	WABASH, IL GIBSON, IN	158	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

FURNISHED EXCAVATION (ILLINOIS SIDE)

STATION	DISTANCE (FT)	END AREA (SQ FT)	AVERAGE END AREA (SQ FT)	VOLUME (CU YD)
1019+79.84		0		
	20.16		112.50	84.00
1020+00.00		225		
	50.00		635.00	1175.93
1020+50.00		1045		
	56.34		1677.50	3500.38
1021+06.34		2310		
	60.00		2380.00	5288.89
1021+66.34		2450		
END OF CONE BENEATH BRIDGE				1768.52
TOTAL				11900

FURNISHED EXCAVATION (INDIANA SIDE)

STATION	DISTANCE (FT)	END AREA (SQ FT)	AVERAGE END AREA (SQ FT)	VOLUME (CU YD)
1050+87.80		2515		
	59.53		2485.00	5478.96
1051+47.33		2455		
	52.67		1887.50	3682.02
1052+00.00		1320		
	50.00		925.00	1712.96
1052+50.00		530		
	45.66		265.00	448.14
1052+95.66		0		
END OF CONE BENEATH BRIDGE				2489.07
TOTAL				13900

EARTH EXCAVATION (INDIANA SIDE)

STATION	DISTANCE (FT)	END AREA (SQ FT)	AVERAGE END AREA (SQ FT)	VOLUME (CU YD)
1048+42.83		1650		
	57.17		1660.00	3514.90
1049+00.00		1670		
	50.00		1632.50	3023.15
1049+50.00		1595		
	50.00		1557.50	2884.26
1050+00.00		1520		
	50.00		1485.00	2750.00
1050+50.00		1450		
	37.33		880.00	1216.68
1050+87.33		310		
	60.00		315.00	700.00
1051+47.33		320		
	52.67		160.00	312.12
1052+00.00		0		
TOTAL				14500

SIGN PANEL-SPECIAL (LANDSCAPING SIGNS)

FROM		TO		SPACING (FT)	QUANTITY (EACH)
STATION	OFFSET	STATION	OFFSET		
1038+18.80	135.3' LT	1042+53.40	135.0' LT	50	9
1042+53.40	135.0' LT	1047+80.20	135.0' LT	50	11
1047+80.20	135.0' LT	1047+80.20	165.0' LT	50	1
1047+80.20	165.0' LT	1050+85.70	139.7' LT	50	6
1038+37.40	55.2' LT	1042+51.90	55.2' LT	50	8
1042+51.90	55.2' LT	1050+85.70	55.3' LT	50	17
TOTAL					52

STABILIZED CONSTRUCTION ENTRANCE

STATION	OFFSET	LOCATION	MEASURED AREA (SQ. FT.)	AREA (SQ. YD.)
1019+04.44	75.54' RT	ILLINOIS SIDE	802	90
1021+97.09	241.53' RT	ILLINOIS SIDE	800	90
1055+12.57	752.57' RT	INDIANA SIDE	865	100
TOTAL				280

02/28/2007 4:04:10 PM m:\p\p\2006\stg\2\10\fig\mesch001.dgn

**benesch**

alfred benesch & company  
 Engineers • Surveyors • Planners  
 205 North Michigan Avenue, Suite 2400  
 Chicago, Illinois 60601  
 312-565-0450  
 Job No: 3428

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SCALE: VERT.      DRAWN BY JNR  
 HORIZ.              CHECKED BY MAC  
 DATE 06/15/07