

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		I000	X071-24	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	02		02	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	120		120	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	400	400		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	686	686		
63500105	DELINEATORS	EACH	12	12		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	18		
67100100	MOBILIZATION	L SUM	1	1		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	400	400		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	60	60		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1525	1525		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1475	1475		
* 72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	54	54		
* 72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	120	120		
* 73400100	CONCRETE FOUNDATIONS	CU YD	2.8	2.8		
* 73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	4	4		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4390	4390		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	18	18		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8	8		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	11	11		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1090	1090		
* A2002416	TREE, BETULA NIGRA HERITAGE (HERITAGE RIVER BIRCH), 2" CALIPER, BALLED AND BURLAPPED	EACH	35	35		
* A2007616	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 2" CALIPER, BALLED AND BURLAPPED	EACH	35	35		

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		I000	X071-24	
* B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	35	35		
X0321781	MECHANICAL SPLICE	EACH	556		556	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1551		1551	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
⊙ Z0076600	TRAINEES	HOOR	500	500		

PLOT DATE = 8/20/2007  
 FILE NAME = c:\projects\94967\shaoq\_94967.dgn  
 PLOT SCALE = 28.0000 / IN.  
 USER NAME = shaoq

© YDBO  
 \* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

Rev.