

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
327	(51-23)B-3	LAWRENCE	56	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

RESURFACING SCHEDULE

STATION TO STATION	LENGTH	PAVEMENT WIDTH	AREA	BITUMINOUS MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL 1/2"	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH) 14 INCH	TEMPORARY RAMP
	FT	FT	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD
STA 54720 TO STA 54725	5	24	13.3	2.1			1.2	173.3			16.8
STA 54725 TO STA 54780	55	24	146.7	21.3	0.1		13.3				
STA 54780 TO STA 54803	23	24	61.3	8.9	0.1	2.0	6.4		65		
STA 54803 TO STA 55134	331	24	882.7	641.3	0.9					883.4	
STA 55134 TO STA 55139	5	24	13.3	9.7						13.3	22.8
BRIDGE OMISSION											
STA 55654 TO STA 55659	5	24	13.3	16.1				266.7		13.3	22.2
STA 55659 TO STA 56101	442	24	1178.7	856.3	1.2				885	1179.6	
STA 56101 TO STA 56345	244	VAR.	0	94.5	0.7	138.0	72.3				
STA 56345 TO STA 56386	41	VAR.	0	26.5	0.2		15.1				
STA 56386 TO STA 56391	5	VAR.	0	3.2			1.7				22.2
TOTALS	1156		2309.3	1680	3	140	110	440	950	2090	84

GUARDRAIL SCHEDULE

	STEEL PLATE BEAM GUARDRAIL, TYPE A	GUARDRAIL REMOVAL	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL, TYPE 6	GUARDRAIL MARKER, TYPE A	TERMINAL MARKER, DIRECT APPLIED
	FT	FT	EACH	EACH	EACH	EACH
LT STA 549+79.1 TO STA 550+29.1			1			1
LT STA 550+29.1 TO STA 551+16.6	87.5	138		1	2	
LT STA 551+16.6 TO STA 551+62.3						1
RT STA 549+62.7 TO STA 550+12.7			1		3	
RT STA 550+12.7 TO STA 551+25.2	112.5	216		1		
RT STA 551+25.2 TO STA 551+70.8						1
LT STA 556+22.5 TO STA 556+68.2			1		4	
LT STA 556+68.2 TO STA 558+30.7	162.5	191		1		
LT STA 556+30.7 TO STA 558+80.7						1
RT STA 556+31.0 TO STA 556+76.6			1		2	
RT STA 556+76.6 TO STA 557+14.1	37.5	141		1		
RT STA 557+14.1 TO STA 557+64.1						
TOTALS	400	686	4	4	11	4

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE(+) SHORTAGE(-)	TOPSOIL EXCAVATION AND PLACEMENT
	CU YD	CU YD	CU YD	CU YD	CU YD
STA 548+00 TO 551+65	4769	3577	1360	2217	614
STA 556+30 TO 562+00	0	0	9629	-9629	988
STRUCTURE EXCAVATION	400	300		300	
COFFERDAM EXCAVATION	335	251		251	
CHANNEL EXCAVATION	12964	9723	38	9685	
TOTALS	18468	13851	11027	2824	1602

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY