F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8899	03-00026-00-RP	MADISON	107	20
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 97295

FINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		
NOTE BOOK NO.		

PAVING SCHEDULE

LOCATION	PROCESS MODIFIED SOIL 12 IN (SQ YD)	LIME (TON)	BIT MATL PR CT (GALLON)	PCC PVT 8 IN (JTD.) (SQ YD)	SUB BASE GRANULAR TY A 4 IN (SQ YD)	AGG BASE CSE TY A 8 IN (SQ YD)	PAVEMENT FABRIC (SQ YD)	HOT-MIX SURF CSE MIX C, N70 (TON)	HOT-MIX BIND CSE IL-19, N70 (TON)
GLEN CROSSING ROAD									
STA. 10+78.09 TO STA. 36+81.24	9383.7	232.2		7520.5	9383.7		7520.5		
STA. 36+81.24 TO STA. 38+81.24	584.0	13.0	146.0			584.0		65.4	65.4
BOLLINGER STREET									
STA. 100+13.00 TO STA. 101+40.00	421.8	10.4		311.5	421.8		311.5		
STA. 101+40.00 TO STA. 101+90.00	140.5	3.5	32.3			140.5		14.5	14.5
CEDAR LANE									
STA. 100+13.00 TO STA. 100+56.93	188.0	4.7		147.0	188.0		147.0		
STA. 100+56.93 TO STA. 101+30.00	184.8	4.6	42.0			148.8		18.8	18.8
JAMIE LYNN DRIVE									
STA. 100+13.00 TO STA. 100+88.00	298.0	7.4		231.6	298.0		231.6		
OAKLAWN ROAD									
STA. 100+13.00 TO STA. 101+88.00	569.0	14.1		482.9	569.0		482.9		
SQUIRE DRIVE									
STA. 100+13.00 TO STA. 101+23.00	520.3	12.9		402.5	520.3		402.5		
WATERFORD LANE									
STA. 100+13.00 TO STA. 100+86.49	323.5	8.0		254.4	323.5		254.4		
TOTAL	12614	311	220	9350	11704	873	9350	99	99

SIGN SCHEDULE

LOCATION	LT / RT	PROPOSED OFFSET (FT)	DESCRIPTION	SIGN PANEL T1 (SQ FT)	METAL POSTS SIGN ASSEMBLY TYPE A (FOOT)	METAL POSTS SIGN ASSEMBLY TYPE B (FOOT)
GLEN CROSSING ROAD						
STA. 12+37.69	RT	23.6	R2-1 / SP-1	8		15.5
STA. 12+63.72	RT	18.6	R1-5L	2.25	12	
STA. 13+21.80	LT	18.6	R1-5L	2.25	12	
STA. 23+80.00	LT	18.6	R2-1 / SP-1	8		15.5
STA. 23+80.00	RT	23.6	R2-1 / SP-1	8		15.5
STA. 36+50.00	LT	18.6	R2-1 / SP-1	8		15.5
BOLLINGER STREET						
STA. 100+27.09	LT	20.0	R1-1	6.25	13	
CEDAR						
STA. 100+29.54	LT	18.5	R1-1	6.25	13	
JAMIE LYNN LANE						
STA. 100+32.54	LT	18.5	R1-1	6.25	13	
OAKLAWN ROAD						
STA. 100+25.33	LT	22.6	R1-1	6.25	13	
SQUIRE						
STA. 100+26.53	LT	31.9	R1-1	6.25	13	
WATERFORD LANE						
STA. 100+28.02	LT	28.6	R1-1	6.25	13	
TOTAL				74	102	62

ORIGINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		
NOTE BOOK NO.		

CHAIN LINK FENCE SCHEDULE

STATION	LENGTH (FOOT)
GLEN CROSSING ROAD	
STA. 20+83.14 TO STA. 22+20.00 LT	160
TOTAL	160

DETECTABLE WARNING SCHEDULE

LOCATION	DETECTABLE WARNING (SQ FT)
GLEN CROSSING ROAD	
STA. 10+50.17 - 22.40' RT TO STA. 10+55.17 - 22.01' RT	11
STA. 10+51.08 - 23.94' LT TO STA. 10+56.38 - 22.95' LT	10
STA. 12+90.16 - 16.08' LT TO STA. 12+95.16 - 18.08' LT	10
STA. 12+92.17 - 16.08' RT TO STA. 12+97.17 - 18.08' RT	10
STA. 13+09.43 - 16.58' RT TO STA. 13+22.51 - 21.58' RT	24
STA. 13+64.36 - 21.58' RT TO STA. 13+78.46 - 16.58' RT	26
STA. 16+13.38 - 18.09' RT TO STA. 16+22.28 - 21.58' RT	25
STA. 16+72.24 - 21.58' RT TO STA. 16+86.14 - 18.09' RT	25
STA. 21+62.78 - 18.08' RT TO STA. 21+76.85 - 21.58' RT	26
STA. 22+21.81 - 21.58' RT TO STA. 22+35.89 - 16.58' RT	26
STA. 25+40.29 - 18.18' RT TO STA. 25+57.09 - 21.58' RT	30
STA. 26+26.32 - 21.58' RT TO STA. 26+43.11 - 18.18' RT	30
STA. 31+35.93 - 18.15' RT TO STA. 31+51.86 - 21.58' RT	29
STA. 32+10.06 - 21.58' RT TO STA. 32+25.98 - 18.15' RT	29
TOTAL	311

PAVEMENT MARKING SCHEDULE

LOCATION	TYPE	POLYUREA 4" YELLOW (FOOT)	POLYUREA 4" WHITE (FOOT)	POLYUREA 6" WHITE (FOOT)	POLYUREA 12" WHITE (FOOT)	POLYUREA LETTERS AND SYMBOLS (SQ FT)
GLEN CROSSING ROAD						
STA. 10+49.67 TO STA. 38+81.24						
	EDGE LINE		4701			
	SKIP DASH 10'-30'	701				
	CROSSWALKS			627		
	STOP BARS				268	
	YIELD LINE					11
TOTAL		701	4701	627	268	11

Juneau Associates, Inc. P.C.
CONSULTING ENGINEERS AND LAND SURVEYORS
2100 State Street, P.O. Box 1325
Granite City, Illinois 62040
Phone:(618)877-1400/(618)452-3535
Fax:(618)452-9541
100 North Research Drive
Edwardsville, Illinois 62025
Phone: (618)656-0500/(618) 656-0800
Fax: (618)659-0941

QUANTITY SCHEDULES
F.A.U. ROUTE 8899
GLEN CROSSING ROAD
GLEN CARBON, ILLINOIS
SECTION No. 03-00026-00-RP

REVISIONS NO.	DATE	BY	REMARKS

SCALE: N.T.S.				
DSN. BY:	BFK	DATE:	12/13/06	SHEET
DWN. BY:	JJB	DATE:	12/13/06	20
CHK'D:	BFK	DATE:	12/13/06	
DWG. NO.	JOB NO. 040630	DGN. NAME: comsch		OF 107 SHTS