

F.A.P. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
343	COOK	24	2
STA. TO STA.		ILLINOIS FED. AID PROJECT	
FED. ROAD DIST. NO.		CONTRACT NO. 60B70	

INDEX OF SHEETS

- S-01 Title Sheet
- S-02 Index of Sheets & Summary of Quantities
- S-03 General Plan - SN 016-2861
- S-04 General Notes & B.O.M. - SN 016-2861
- S-05 Stage Construction Deck Sections - SN 016-2861
- S-06 Screed Plan & Top of Deck Elevations - SN 016-2861
- S-07 Top of Deck Elevations - SN 016-2861
- S-08 Deck Cross Section - SN 016-2861
- S-09 Framing Plan & Moment Table - SN 016-2861
- S-10 Girder Elevation & Steel Details - SN 016-2861
- S-11 Bearing Details - SN 016-2861
- S-12 General Plan - SN 016-2732
- S-13 General Notes & B.O.M. - SN 016-2732
- S-14 Stage Construction Deck Sections - SN 016-2732
- S-15 Screed Plan & Top of Deck Elevations - SN 016-2732
- S-16 Top of Deck Elevations - SN 016-2732
- S-17 Deck Cross Section - SN 016-2732
- S-18 Strip Seal Joint - SN 016-2732
- S-19 Framing Plan & Moment Table - SN 016-2732
- S-20 Girder Elevation & Steel Details - SN 016-2732
- S-21 Bearing Details - SN 016-2732
- S-22 Existing SN 016-0523 Plan
- S-23 Deck Beam Removal & Replacement
- S-24 Deck Beam Details

SUMMARY OF QUANTITIES

URBAN
801. FED. 201. STATE

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE		
				SN 016-2861	SN 016-2732	SN 016-0523
M5050120	Furnishing Structural Steel	L.S.	1	0.55	0.45	0
50300410	Furnishing Elastomeric Assembly, Type I	EACH	21	11	10	0
X0322388	Storage of Structural Steel and Bearings	UNIT	538	296	242	0
MX033722	Furnish Precast Prestressed Concrete Deck Beam, (686 MM Depth)	SQ M	12.58	0	0	12.58

* For Storage of Structural Steel, One UNIT shall be Equal to 5 Metric Tons the Quantity was Calculated Based on the Assumption that 25% of the Steel Mass has to be Stored for 30 Calendar Days.

SHT. S-02 OF S-24

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
IL ROUTE 68 OVER US-14 & UPRR
F.A.P. ROUTE 343 SECTION 70HB-F & 70D-Y-B-F
COOK COUNTY
STRUCTURE NO. 016-2861 & 016-2732
INDEX OF SHEETS & SUMMARY OF QUANTITIES

DESIGNED: BTO DRAWN: BTO
DATE: 6/06 CHECKED: JAN CHECKED: JAN

1454.01.15200 000 01/22/06 06 4 41 51 PM