

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 344	540 R-PCC-PP-1	COOK	19	4

URBAN

SUMMARY OF QUANTITIES

CONTRACT 60C41

100% STATE  
CONSTRUCTION  
TYPE CODE  
J000

CODE NUMBER.	DESCRIPTION	UNIT	TOTAL
42001300	PROTECTIVE COAT	SQ YD	1810
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500
44003100	MEDIAN REMOVAL	SQ FT	1396
44200966	CLASS B PATCHES, TYPE I, 10 INCH	SQ YD	4
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	296
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	580
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	846
44213100	PAVEMENT FABRIC	SQ YD	1426
44213200	SAW CUTS	FOOT	6475
60624600	CORRUGATED MEDIAN	SQ FT	1396
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	LSUM	1
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	800
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48
Z0017202	DOWEL BARS 1 1/2"	EACH	1720
Z0075325	TIE BARS 1"	EACH	1190

\* SPECIALTY ITEMS

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES