

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
870	534 R-1-T	WILL	42	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN I000 100% STATE					
20100310	TREE REMOVAL, SPECIAL (6 TO 15 UNITS DIAMETER)	UNIT	5	5					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	6	6					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	6	6					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	6	6					
25200110	SODDING, SALT TOLERANT	SQ YD	450	450					
25200200	SUPPLEMENTAL WATERING	UNIT	5	5					
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	180	180					
35200600	EARTH EXCAVATION	CU YD	400	400					
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	155	155					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	16	16					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	28	28					
44000100	PAVEMENT REMOVAL	SQ YD	155	155					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	950	950					
44003100	MEDIAN REMOVAL	SQ FT	155	155					
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	60	60					
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1					
50200500	COFFERDAMS	EACH	1	1					
50800105	REINFORCEMENT BARS	POUND	44240	44240					
50800515	BAR SPLICERS	EACH	198	198					
51205200	TEMPORARY SHEET PILING	SQ FT	878	878					
54002020	EXPANSION BOLTS 3/4 INCH	EACH	118	118					
54003000	CONCRETE BOX CULVERTS	CU YD	131.7	131.7					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	950	950					
60624600	CORRUGATED MEDIAN	SQ FT	155	155					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1					
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6001	6001					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN I000 100% STATE					
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	4030	4030					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1300	1300					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	300	300					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	160	160					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2805	2805					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	530	530					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	40	40					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4					
78300400	THERMOPLASTIC PAVEMENT MARKING REMOVAL	SQ FT	1200	1200					
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	844	844					
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	112	112					
* 81400100	HANDHOLE	EACH	1	1					
* 81900205	TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)	FOOT	844	844					
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	2					
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	310	310					
* 87900200	DRILL EXISTING HANDHOLE	EACH	7	7					
* 88600100	DETECTOR LOOP, TYPE I	FOOT	72	72					
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1					
* X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1379.5	1379.5					
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	60	60					
X0325205	MONODIRECTIONAL REFLECTORS TYPE C	EACH	20	20					
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	48	48					
X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1	1					
* X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1	1					
X0712400	TEMPORARY PAVEMENT	SQ YD	610	610					

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev.

PLOT DATE: 9/4/2007

9/4/2007 9:44:18 AM C:\Users\jason\Documents\62556\62556.dwg