

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
351	537 R-1	COOK	245	4
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE												
				100% STATE		100% VILLAGE		95% STATE 5% VILLAGE		100% STATE		100% VILLAGE		100% VILLAGE		50% STATE 50% VILLAGE NEW SIDEWALK
				ROADWAY	TRAFFIC SIGNALS US6/US45	TRAFFIC SIGNALS US45/158+HPL.	TRAFFIC SIGNALS US6/94+H.V.	100% STATE INTER CONNECT	100% STATE SIGNAL PRE EMPTION	LIGHTING	WATER MAIN	SANITARY SEWER	VILLAGE LANDSCAPE	RETAINING WALL		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	205	J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y030-1E	Y060	Y060	Y003	Y007	SFTY-1B
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	50	205												
20101000	TEMPORARY FENCE	FOOT	100	100												
* 20101100	TREE TRUNK PROTECTION	EACH	10	10												
* 20101200	TREE ROOT PRUNING	EACH	20	20												
20200100	EARTH EXCAVATION	CU YD	15,290	15,290												
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	9,700	9,700												
20400800	FURNISHED EXCAVATION	CU YD	3,050	3,050												
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	8,885	8,885												
20800150	TRENCH BACKFILL	CU YD	4,722	4,722												
* 21101625	TOPSOIL-FURNISH AND PLACE 6"	SQ YD	15,971	15,971												
* 25000110	SEEDING, CLASS 1A	ACRE	3.50	3.50												
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	335	335												
* 25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	335	335												
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	335	335												
25000750	MOWING	ACRE	3.50	3.50												
* 25100630	EROSION CONTROL BLANKET	SQ YD	230	230												
* 25200200	SUPPLEMENTAL WATERING	UNIT	180.0	180.0												
* 25301700	SHRUBS	EACH	818												818	
* 25400105	PERENNIAL PLANTS	EACH	11,950												11,950	
28000300	TEMPORARY DITCH CHECKS	EACH	4	4												
28000510	INLET FILTERS	EACH	73	73												
* 28000600	SEEDING, CLASS 7	ACRE	0.50	0.50												
28100109	STONE RIPRAP CLASS A5	SQ YD	150	150												
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	360	360												
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	360	360												

*SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION US RTE 6 (159TH ST) AT US RTE 45 (LAGRANGE RD)
NAME	DATE	
		SUMMARY OF QUANTITIES
		SCALE: N/A
		DATE: 7-07-06
		DRAWN BY: BFH
		CHECKED BY: RCH
		McDonough Associates Inc. Engineers / Architects

F:\Dgn\sq01001.sht
 7/31/2006
 9:35:14 AM