

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE												
				100% STATE		100% VILLAGE		95% STATE 5% VILLAGE		100% VILLAGE						
				ROADWAY	TRAFFIC SIGNALS US6/US45	TRAFFIC SIGNALS US45/158+thPL	TRAFFIC SIGNALS US6/94+thAV.	100% STATE INTER CONNECT	100% VILLAGE SIGNAL PRE EMPTION	LIGHTING	WATER MAIN	SANITARY SEWER	VILLAGE LANDSCAPE	RETAINING WALL	50% STATE 50% VILLAGE SIDEWALK	
40600990	TEMPORARY RAMP	SQ YD	360	J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y030-1E	Y060	Y060	Y003	Y007	SFTY-1B
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	1,171													
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	44,674	44,674												
42001300	PROTECTIVE COAT	SQ YD	10,002	10,002												
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	2,622	2,622												
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	56655	36833												19,822
44000100	PAVEMENT REMOVAL	SQ YD	38,269	38,269												
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	8,406	8,406												
44000300	CURB REMOVAL	FOOT	5,281	5,281												
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	16,378	16,378												
44000600	SIDEWALK REMOVAL	SQ FT	25,536	25,536												
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	837	837												
44003100	MEDIAN REMOVAL	SQ FT	30,556	30,556												
50901105	STEEL RAILING	FOOT	1,242												1,242	
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	397	397												
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12	FOOT	2,582	2,582												
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15	FOOT	752	752												
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18	FOOT	903	903												
55021900	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 21	FOOT	268	268												
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24	FOOT	737	737												
55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30	FOOT	764	764												
55100500	STORM SEWER REMOVAL 12"	FOOT	2,313	2,313												
55100700	STORM SEWER REMOVAL 15"	FOOT	970	970												
55100900	STORM SEWER REMOVAL 18"	FOOT	452	452												
55101200	STORM SEWER REMOVAL 24"	FOOT	1,632	1,632												
55101300	STORM SEWER REMOVAL 27"	FOOT	19	19												

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
US RTE 6 (159TH ST) AT US RTE 45 (LAGRANGE RD)

SUMMARY OF QUANTITIES

SCALE: N/A
DATE: 7-07-06

DRAWN BY: BFH
CHECKED BY: RCH

McDonough Associates Inc.
Engineers / Architects

I:\Dep\sq01002.sht
7/31/2006
10:53:06 AM