


F.A.P. RY.:	SECTION	COUNTY	TOTAL SHEET	SHEET NO.
351	537 R-1	COOK	245	7
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	CONTRACT NO. 62-80

SUMMARY OF QUANTITIES



CODE NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE													
				ROADWAY	TRAFFIC SIGNALS US6/US45	TRAFFIC SIGNALS US45/158thPL.	TRAFFIC SIGNALS US6/94thAV.	100% STATE INTER CONNECT	100% VILLAGE SIGNAL PRE EMPTION	LIGHTING	WATER MAIN	SANITARY SEWER	VILLAGE LANDSCAPE	RETAINING WALL	50% STATE 50% VILLAGE NEW SIDEWALK		
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y030-1E	Y060	Y060	Y003	Y007	SFTY-1B		
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2													
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2													
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1													
60260050	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	2										2				
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	19	19													
60266500	VALVE VAULTS TO BE REMOVED	EACH	7	3								4					
60500040	REMOVING MANHOLES	EACH	20	20													
60500050	REMOVING CATCH BASINS	EACH	55	55													
60500705	CATCH BASINS TO BE FILLED TO MAINTAIN FLOW	EACH	2	2													
60600605	CONCRETE CURB, TYPE B	FOOT	2128	2128													
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	482	482													
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	6823	6823													
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	10106	10106													
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	1416	1416													
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	22,897	22,897													
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	1,964	1,964													
60619910	CONCRETE MEDIAN, TYPE SB-6.18	SQ FT	6,433	6,433													
60622800	CONCRETE MEDIAN, TYPE SM-6.12	SQ FT	1,736	1,736													
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	337.5	337.5													
* 63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	25.0	25.0													
67000400	ENGINEER'S FIELD OFFICE TYPE A	CAL MO	12	12													
67100100	MOBILIZATION	L SUM	1	1													
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1													
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	360	360													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,310	2,310													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	34,008	34,008													

* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION US RTE 6 (159TH ST) AT US RTE 45 (LAGRANGE RD)
NAME	DATE	

SUMMARY OF QUANTITIES

SCALE: N/A DRAWN BY: BFH
DATE: 7-07-06 CHECKED BY: RCH

McDonough Associates Inc.
Engineers / Architects

I:\Data\01004.sht
7/31/2008
9:45:11 AM

Rev.