	SUMMARY OF QUANTITIES			1001/STATE		100% YILLAGE				*	90% YILLAG	STA FED. ROAD	SECTION 537 R-1 TO IST. NO ILLINO	COOK O STA OS FED. AID F	PROJE :: T
CODE NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS US6/US45		SIGNALS	INTER CONNECT	SIGNAL PRE EMPTION	LIGHTING	WATER MAIN	SANITARY SEWER	VILLAGE LANDSCAPE	RETAINING WALL	SO!STATE SO!YILLAGE NEW SIDEWALK
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F		Y030-1E	Y060	Y060	Y003	Y007	SFTY-1B
X0323840	WATER MAIN LINE STOP 6"	EACH	1				****				1				
X0323842	WATER MAIN LINE STOP 12"	EACH	1								1				
X0323870	TRANSITION SLEEVE 8"	EACH	1								1				
X0323871	TRANSITION SLEEVE 12"	EACH	5								5				
X0323873	TRANSITION SLEEVE 10"	EACH	1								1				
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	8,080	8,080											-
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	8,080	8,080											
X0324302	REMOVAL OF TEMPORARY LIGHTING FIXTURE, SALVAGE	EACH	75		·					75					
X0840000	SANITARY SEWER REMOVAL 8"	FOOT	230									230			
X0976500	END SECTIONS TO BE REMOVED	EACH	3	3										<u> </u>	
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	25	25											
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	48	48											
X7030104	WET PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	68,477	68,477											
X7030106	WET PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	10,266	10,266											
X7030112	WET PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	1,930	1,930											
														<u> </u>	
X7030120	WET PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	2,598	2,598											<u> </u>
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	3		1	1	1								
X8160370	UNIT DUCT, WITH 3-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (EPR-TYPE RHW), 1 1/4" DIA., POLYETHYLENE	FOOT	1,328							1,328					
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	11,681					11,681							
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	2,902						2,902						
X8800020	SIGNAL HEAD ,LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	30		15	11	4								
X8800040	SIGNAL HEAD ,LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3		3										
X8800045	SIGNAL HEAD ,LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	20		5	3	12								
X8805280	SIGNAL HEAD ,LED, 2-FACE, 1-3 SECTION, 1-5, SECTION BRACKET MOUNTED	EACH	1			1									
					-					1	-				
X8805310	SIGNAL HEAD ,LED, 3-FACE, 1-3 SECTION, 2-5, SECTION BRACKET MOUNTED	EACH	1			1									
X8810610	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	4	1	4			<u></u>	1		<u> </u>	<u> </u>		<u>L</u>	

REVISIONS
NAME DATE
US RTE 6 (159TH ST) AT US RTE 45 (LAGRANGE RD) SUMMARY OF QUANTITIES SCALE: N/A DRAWN BY: BFH SCALE: N/A

DATE: 7-07-08

CHECKEU DI:

McDonough Associates Inc.

Engineers / Architects

SO CHECKED BY: RCH

SQ-9