

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	100% STATE		100% VILLAGE		95% STATE 5% VILLAGE		100% VILLAGE					CONSTRUCTION TYPE CODE	
				ROADWAY	TRAFFIC SIGNALS US6/US45	TRAFFIC SIGNALS US45/158thPL.	TRAFFIC SIGNALS US6/94thAV.	100% STATE INTER CONNECT	100% VILLAGE SIGNAL PRE EMPTION	LIGHTING	WATER MAIN	SANITARY SEWER	VILLAGE LANDSCAPE	RETAINING WALL		
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y030-1E	Y060	Y060	Y003	Y007		SFT Y-1B
X0325542	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	1,000	1,000												
* X0325543	TRANSITION SLEEVE 16"	EACH	1									1				
* X0325544	PRESSURE CONNECTION 16" X 8"	EACH	1									1				
* X0323828	WATER MAIN TO BE REMOVED 16"	FOOT	1,023									1,023				
* X0320772	WATER MAIN TO BE REMOVED 12"	FOOT	132									132				
* X0325548	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 26 FT. AND 38 FT.	EACH	1				1									
* X0325549	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 32 FT. AND 36 FT.	EACH	1			1										
* X0325550	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 36 FT. AND 38 FT.	EACH	1			1										
* X0325551	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 44 FT AND 22 FT.	EACH	1				1									
* X0325552	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 44 FT AND 28 FT.	EACH	1				1									
* X0325545	PLANTING MIX, FURNISH AND PLACE, 18"	SQ YD	1,072											1,072		
* A2002020	TREE, AESCULUS GLABRA (OHIO BUCKEYE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	12												12	
* A2002218	TREE, ALNUS GLUTINOSA (BLACK ALDER), 2" CALIPER, BALLED AND BURLAPPED	EACH	32												32	
* A2004514	TREE, GINKGO BILOBA AUTUMN GOLD (AUTUMN GOLD GINKGO), 2-1/2", BALLED AND BURLAPPED	EACH	5												5	
* X0325553	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 20 FT. MAST ARM	EACH	75									75				
XX005840	FLAGSTONE SIDEWALK (SPECIAL)	SQ FT	2,876												2,876	
* X0325559	LIGHTING CONTROLLER, SPECIAL, 200A, 240/480V	EACH	1									1				
* X0325555	ALUMINUM BREAKAWAY, TRANSFORMER BASE	EACH	60									60				
* X0325556	TEMPORARY LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT, TYPE III DISTRIBUTION	EACH	9									9				
* X0325557	TEMPORARY LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT, TYPE IV DISTRIBUTION	EACH	75									75				
* X0325558	UNIT DUCT, WITH 5-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (EPR-TYPE RHW), 1 1/2" DIA., POLYETHYLENE	FOOT	10,650									10,650				
* X0325554	MODIFY EXISTING LIGHT POLE, ALUMINUM 47.5 FT. M.H., WITH NEW 15 FT. MAST ARM AND 20A, 120V GFCI RECEPTACLE	EACH	42									42				
X2510630	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	15971												15,971	
42400800	DETECTABLE WARNINGS	SQ FT	350	350												
06900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1375	1375												
06900400	SPECIAL WASTE GROUNDWATER DISPOSAL	GALLON	12,046	12,046												
06900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1												
06901000	BACKFILL PLUGS	CU YD	90	90												
X03D1828	ENGINEERED BARRIER	SQ YD	2,600	2,600												

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
US RTE 6 (159TH ST) AT US RTE 45 (LAGRANGE RD)

SUMMARY OF QUANTITIES

SCALE: N/A
DATE: 7-07-06

DRAWN BY: BFH
CHECKED BY: RCH

McDonough Associates Inc.
Engineers / Architects

Rev. 9-11-06

Dgn: sq01011.sht
7/31/2006
11:57:46 AM