

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2592	531-T	COOK	10	3

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN					
				100% STATE					
				SFTY-2A	SFTY-3N				
20101700	SUPPLEMENTAL WATERING	UNIT	10	10					
20200100	EARTH EXCAVATION	CU YD	72	72					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	65	65					
25000210	SEEDING, CLASS 2A	ACRE	0.05	0.05					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10					
25002300	TEMPORARY SEEDING	ACRE	0.05	0.05					
25100630	EROSION CONTROL BLANKET	SQ YD	65	65					
28000400	PERIMETER EROSION BARRIER	FOOT	180	180					
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	27	27					
42101300	PROTECTIVE COAT	SQ YD	240	240					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	540	540					
44000600	SIDEWALK REMOVAL	SQ FT	540	540					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	108	108					
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	144	144					
44213200	SAW CUTS	FOOT	396	396					
50102400	CONCRETE REMOVAL	CU YD	30.2	30.2					
50800105	REINFORCEMENT BARS	POUND	8860	8860					
54003000	CONCRETE BOX CULVERTS	CU YD	27.0	27.0					
63301000	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL	FOOT	108	108					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	220	220					
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	15	15					
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48					
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	266	266					
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	143	143					
*XX006058	POLYUREA PAVEMENT MARKING - LINE 4"	FOOT	20	20					
Z0017100	DOWEL BARS	EACH	40	40					
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 2	EACH	2	2		2			
Z0075325	TIE BARS 1"	EACH	212	212					
20201550	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	72	72					

9/12/2006 10:58:00 AM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 9/12/2006

*SPECIALTY ITEMS

Rev.